

CITY OF TUCKER

ACKNOWLEDGE RECEIPT OF ADDENDUM #1

ITB 2025-010
FALL 2025 RESURFACING

Please complete this page and include this page only in bid submittal.

**I hereby acknowledge receipt of the supplement pertaining to the
above referenced bid.**

COMPANY NAME: _____

CONTACT PERSON: _____

ADDRESS: _____

CITY: _____ **STATE:** _____ **ZIP:** _____

PHONE: _____ **FAX:** _____

EMAIL ADDRESS: _____

SIGNATURE

DATE

ITB 2025-010
ADDENDUM #1

This addendum contains the following:

- Response to Questions received
 - Revised Detailed Estimates
- This supersedes the Detailed Estimates in the original bid document.

	QUESTION	ANSWER
1	Would the City allow the use of LASA in lieu of Hydrated Lime per the attached GDOT Bulletin?	No, Hydrated Lime is to be used on this project.
2	Can the city separate the Patching and 19mm @ 1.75 inches items? Since the patching will include milling and haul off.	No. The patching price should include the milling, haul off, and 19mm asphalt in one unit ton price

	Street	From Street	To Street	Length (ft)	Width (ft)	Square Yards	Estimated Patching Ton	Estimated 9.5 MM, 2" Lift	
1	Oswood Ct	END	END	1,975	26.5	5,815	120	640	
2	Oswood Dr	Chamblee Tucker Rd	Oswood Ct	1,649	26.5	4,854	100	534	
3	Empress Court	Imperails Hills Drive	END	365	24	973	70	107	
4	Imperial Hills Dr	Chamblee Tucker Rd	Oswood Ct	1,150	24	3,067	110	337	
5	Doaks Run Ct	END	Oswood Ct	950	26.5	2,797	80	308	
6	Imperial Hills Ct	END	Imperial Hills Dr	550	25	1,528	90	168	
	Street	From Street	To Street	Length (ft)	Width (ft)	Square Yards	Estimated Patching Ton	Estimated 9.5 MM, 2" Lift	
7	Lake Ivanhoe Dr	Templar Knight Dr	West Hampton Woods Drive	2,610	27	7,830	160	861	
8	Westhampton Way	Westhampton Cir	Old Norcross Rd	760	25	2,111	90	232	
9	Whippoorwill Ct	END	Westhampton Cir	245	24	653	50	72	
10	Westhampton Cir	West Hampton Dr	END	1,720	25	4,778	135	526	
11	Crest Rd	Old Norcross Rd	West Hampton Drive	1,130	25	3,139	120	345	
12	Esquire Way	Leonora Dr	Crest Rd	1,067	27	3,142	120	346	
13	Crest Ct	Crest Rd	END	350	25	972	70	107	
14	Westhampton Dr	Crest Rd	END	2,645	25	7,347	195	808	
15	Westhampton Woods Dr	END	END	430	26	1,242	40	137	
16	Leonora Dr	Old Norcross Rd	West Hampton Drive	1,830	27	5,490	160	604	
17	N Hudlow Ct	Leonora Dr	END	260	24	693	36	76	
18	S Hudlow Ct	END	N Hudlow Ct	225	24	600	36	66	
19	Leonora Ct	Leonora Dr	END	285	24	760	40	84	
	Street	From Street	To Street	Length (ft)	Width (ft)	Square Yards	Estimated Patching Ton	Estimated 9.5 MM, 2" Lift	
20	Oxbow Rd	Deer Ridge Dr	Rosser Road	3,900	24	10,400	250	1144	
21	Antelope Ln	Oxbow Rd	Flintlock Dr	4,500	24	12,000	195	1320	
22	Fawn Rdg	Antelope Ln	END	1,375	24	3,667	140	403	
23	Oxbow Cir	Oxbow Rd	Oxbow Rd	2,151	24	5,736	85	631	
24	Pheasant Run	Fawn Rdg	END	1,925	24	5,133	105	565	
25	Flintlock Dr	Oxbow Road	Pheasant Run	1,520	24	4,053	145	446	
	Street	From Street	To Street	Length (ft)	Width (ft)	Square Yards	Estimated Patching Ton	Estimated 9.5 MM, 2" Lift	
26	Cowan Rd	Idlewood Rd	Hugh Howell Road						
27	Hanfred Ln	Hanfred Ct	Dillard St	1,280	25	3,556	80	391	
28	Hanfred Court	Hanferd Lane	END	655	25	1,819	40	200	
29	Dillard St	Dillard St	Cowan Rd	1,375	25	3,819	65	420	
				Length (ft)	Width (ft)	Square Yards	Estimated Patching Ton	19 MM Binder 1.75"	12 MM @ 1.375"
	* Cowan Road is 3" mill with 1.75" binder&12.5mm topping at (1 and 3/8)			1,930	25	5,361	140	516	407
				TOTAL LF		TOTAL SY	TOTAL PATCH	HMA TOTAL	
				40,807		113,338	3067	12801	