

013933005_01.dgn 7/2/2025 Ali.Donnes plotborder-ORD-PO.tbl EORG THE DRAWINGS AS LISTED BELOW HAVE BEEN SIGNED AND SEALED BY (% No. 39533 PROFESSIONAL DARREN WILTON PE No 039533 KIMLEY-HORN AND ASSOCIATES, INC. SUITE 350, 3930 EAST JONES BRIDGE ROAD PEACHTREE CORNERS, GA 30092 CERTIFICATE OF AUTHORIZATION #:PEF000379 CERTIFICATE OF AUTHORIZATION EXPIRATION DATE:06/30/2026 7/15/2025 DRAWING DESCRIPTION
COVER DRAWING
SIGNATURE DRAWING
INDEX DRAWING
REVISION SUMMARY DRAWING
GENERAL NOTES
TYPICAL SECTIONS
SUMMARY OF QUANTITIES
CONSTRUCTION LAYOUT
CONSTRUCTION PLAN
MAINLINE ROADWAY PROFILE
CROSSROAD PROFILE
DRIVEWAY PROFILES
DRIVEWAY PROFILES
SPECIAL GRADING DRAWING
CONSTRUCTION STAGING DRAWINGS
DRAINAGE PROFILES
UTILITY PLANS
LIGHTING PLANS AND DETAILS
SIGNAL PLANS
SIGNAL PLANS
SIGNAL PLANS
SPECIAL CONSTRUCTION DETAIL
EROSION CONTROL COVER DRAWING
EROSION SEDIMENTATION AND POLLUTION CONTROL GENERAL NOTES DRAWING
EROSION SEDIMENTATION AND POLLUTION CONTROL GENERAL NOTES DRAWING
EROSION CONTROL COVER DRAWING
EROSION CONTROL COVER DRAWING
EROSION CONTROL DETAILS
EROSION CONTROL COVER DRAWING
EROSION CONTROL DETAILS
EROSION CONTROL WATERSHED MAP AND SITE MONITORING LOCATION DRAWING No. - 04-0002 - 05-0005 - 06-0002 - 11-0003 - 13-0005 - 15-0002 - 16-0003 - 51-0011 - 54-0020 NOTE: DRAWINGS IN SECTIONS 40, 41, 52, AND 56 ARE GDOT STANDARDS AND DETAILS AND ARE NOT COVERED BY THIS SIGNATURE AND SEAL. DRAWINGS IN SECTION 38 CONTAIN GDOT SPECIAL DESIGN DETAILS AND ARE NOT COVERED BY THIS SIGNATURE AND SEAL UNLESS OTHERWISE LISTED IN THE ABOVE DRAWING LIST. REVISION DATES SIGNATURE SHEET Kimley»Horn IDLEWOOD RD AT FELLOWSHIP RD Engineering, Planning, And Environmental Consultants 3930 East Jones Brldge Road, Sulte 350 DRAWING No. Peachtree Corners, Georgia 30092 NOT TO SCALE

Description				
01-0002 Signature Drawing S1-0001 TO 51-0011 ESPCP General Notes	Drawing Number	Drawing Description	Erosion Control Plan	
02-0001 Index Drawing	01-0001	Cover Sheet	50-0001	Erosion Control Cover Drawing
03-0001 Revision Summary Drawing 52-0002 Const. Detail (EC-L2) - Erosion Control legend and Uniform Code Sheet (Sheet 2 05-0001 TO 05-0005 Typical Sections 52-0004 Const. Detail (EC-L3) - Erosion Control legend and Uniform Code Sheet (Sheet 3 05-0001 TO 05-0005 Const. Detail (EC-L3) - Erosion Control legend and Uniform Code Sheet (Sheet 4 05-0001 TO 11-0002 Summary of Quantities 52-0005 Const. Detail (EC-L4) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 13-0005 Construction Layout 52-0006 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 13-0005 Construction Plan 52-0006 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 13-0005 Construction Plan 52-0007 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 13-0005 Construction Plan 52-0006 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 13-0005 Construction Plan 52-0007 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 13-0005 Construction Plan 52-0007 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 13-0005 Construction Plan 52-0007 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0007 Construction Exit S2-0007 Construction Plan Espect portion Construction Plan S2-0007 Construction Exit S2-0007 Construction Exit S2-0001 TO 13-0003 Entwemper Profiles S3-0001 TO 33-0001 Espect portion Construction Exit Ec-L5 - Erosion Control Detail S2-0007 Construction Exit S2-0001 TO 33-0001 Espect portion Construction	01-0002	Signature Drawing	51-0001 TO 51-0011	ESPCP General Notes
04-0001 TO 04-0002 General Notes 52-0003 Const. Detail (EC-L3) - Erosion Control legend and Uniform Code Sheet (Sheet 3 of 50-0001 TO 05-0005 Typical Sections 52-0004 Const. Detail (EC-L4) - Erosion Control legend and Uniform Code Sheet (Sheet 4 of 50-0001 TO 06-0002 Summary of Quantities 52-0005 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 5 of 50-0001 TO 13-0005 Construction Layout 52-0006 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 5 of 50-0001 TO 13-0005 Construction Plan 52-0007 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 6 of 50-0001 TO 13-0005 Construction Plan 52-0007 Const. Detail (EC-L7) - Erosion Control legend and Uniform Code Sheet (Sheet 7 of 50-0001 TO 13-0005 Construction Plan Espect Data and Uniform Code Sheet (Sheet 7 of 50-0001 TO 13-0005 Construction Plan Espect Data and Uniform Code Sheet (Sheet 7 of 50-0001 TO 13-0005 Construction Staging Plans 54-0001 TO 54-0020 Espect Data and Uniform Code Sheet (Sheet 7 of 50-0001 TO 13-0005 Construction Staging Plans 56-0001 TO 13-0020 Espect Data and Uniform Code Sheet (Sheet 5 of 50-0001 TO 13-0005 Construction Staging Plans 56-0001 TO 13-0002 Construction Staging Plans 56-0001 TO 13-0005 Construction Staging Plans 56-0001 TO 13-0005 Construction Staging Plans 56-0004 TO 24-0005 TO 13-0006 TO 13-000	02-0001	Index Drawing	52-0001	Const. Detail (EC-L1) - Erosion Control legend and Uniform Code Sheet (Sheet 1
05-0001 TO 05-0005 Typical Sections 52-0004 Const. Detail (EC-L4) - Erosion Control legend and Uniform Code Sheet (Sheet of Sections 11-0001 TO 11-0003 Construction Layout 52-0005 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet of Sections 13-0001 TO 13-0005 Construction Plan 52-0006 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet of Sections 13-0001 TO 13-0005 Construction Plan 52-0006 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet of Sections 13-0001 TO 13-0005 Construction Plan 52-0006 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet of Sections 13-0001 TO 13-0005 Construction Plan ESPCP Drainage Area Map S4-0001 TO 54-0005 Special Grading 53-0001 ESPCP Drainage Area Map S4-0001 TO 54-0005 EC Watershed Map-Site Monitoring Plan 55-0001 EC Watershed Map-Site Monitoring Plan 55-0001 EC Watershed Map-Site Monitoring Plan 55-0001 D-24A Temporary Silt Fence Hook, Inlet Sediment Traps 56-0003 D-24C Temporary Silt Fence Hook, Inlet Sediment Traps 56-0003 D-34 Construction Exit 56-0004 D-54 Sod Installation 56-0004 D-54 Sod Installation 56-0004 Construction Exit 56-0004 Construction Exit 56-0004 Construction Exit 56-0005 Const. Detail (EC-L1) - Erosion Control legend and Uniform Code Sheet (Sheet of Sheet of S	03-0001	Revision Summary Drawing	52-0002	Const. Detail (EC-L2) - Erosion Control legend and Uniform Code Sheet (Sheet 2
06-0001 TO 06-0002 Summary of Quantities 52-0005 Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 5 11-0001 TO 11-0003 Construction Layout 52-0006 Const. Detail (EC-L6) - Erosion Control legend and Uniform Code Sheet (Sheet 6 13-0001 TO 15-0005 Const. Detail (EC-L6) - Erosion Control legend and Uniform Code Sheet (Sheet 7 15-0001 TO 15-0002 Sepon To Sa-0001 To Sheet (Sheet 7 15-0007 TO Sheet (Sheet 7 15-0001 TO 15-0002 TO Sheet (Sheet 7 15-0001 TO 15-0002 TO Sheet (Sheet 7 15-0001 TO Sheet To Sheet (Sheet 7 15-0001 TO Sheet To	04-0001 TO 04-0002	General Notes	52-0003	Const. Detail (EC-L3) - Erosion Control legend and Uniform Code Sheet (Sheet 3
11-001 TO 11-0003 Construction Layout 52-0006 Const. Detail (EC-L6) - Erosion Control legend and Uniform Code Sheet (Sheet of Sheet of Shee	05-0001 TO 05-0005	Typical Sections	52-0004	Const. Detail (EC-L4) - Erosion Control legend and Uniform Code Sheet (Sheet 4
13-0001 TO 13-0005 Construction Plan 52-0007 Const. Detail (EC-L7) - Erosion Control legend and Uniform Code Sheet (Sheet 7 15-0001 TO 15-0002 Mainline Profile 53-0001 ESPCP Drainage Area Map 54-0001 TO 54-0020 BMP Location Details 55-0001 EC Watershed Map-Site Monitoring Plan Erosion Control Details 55-0001 EC Watershed Map-Site Monitoring Plan Erosion Control Details 55-0001 EC Watershed Map-Site Monitoring Plan Erosion Control Details 55-0001 EC Watershed Map-Site Monitoring Plan Erosion Control Details 56-0001 D-24A Temporary Silt Fence 56-0002 D-24A Temporary Silt Fence 56-0002 D-24C Temporary Silt Fence 56-0002 D-24C Temporary Silt Fence 56-0003 D-41 Construction Exit 56-0001 D-55A Riprap Outlet Protection 56-0005	06-0001 TO 06-0002	Summary of Quantities	52-0005	Const. Detail (EC-L5) - Erosion Control legend and Uniform Code Sheet (Sheet 5
15-0001 TO 15-0002	11-0001 TO 11-0003	Construction Layout	52-0006	Const. Detail (EC-L6) - Erosion Control legend and Uniform Code Sheet (Sheet 6
16-0001 TO 16-0003 Crossroad Profile 54-0001 TO 54-0020 BMP Location Details	13-0001 TO 13-0005	Construction Plan	52-0007	Const. Detail (EC-L7) - Erosion Control legend and Uniform Code Sheet (Sheet 7
17-001 Driveway Profiles 55-001 EC Watershed Map-Site Monitoring Plan	15-0001 TO 15-0002	Mainline Profile	53-0001	ESPCP Drainage Area Map
18-0001 TO 18-0009 Special Grading Erosion Control Details 19-0001 TO 19-0015 Construction Staging Plans 56-0001 D-24A Temporary Silt Fence 22-0001 TO 22-0002 Drainage Profiles 56-0002 D-24C Temporary Silt Fence J-Hook, Inlet Sediment Traps 23-0001 TO 23-0013 Earthwork Cross Sections 56-0003 D-41 Construction Exit 24-0001 TO 24-0005 Utility Plans 56-0004 D-54 Sod Installation 25-0001 TO 25-0004 Lighting Plans 56-0005 D-55A Riprap Outlet Protection 26-0001 TO 26-0006 Signing and Marking Plans 56-0005 Signal Plans	16-0001 TO 16-0003	Crossroad Profile	54-0001 TO 54-0020	BMP Location Details
19-0001 T0 19-0015 Construction Staging Plans 56-0001 D-24A Temporary Silt Fence 22-0001 T0 22-0002 Drainage Profiles 56-0002 D-24C Temporary Silt Fence J-Hook, Inlet Sediment Traps 23-0001 T0 23-0013 Earthwork Cross Sections 56-0003 D-41 Construction Exit 24-0001 T0 24-0005 Utility Plans 56-0004 D-54 Sod Installation 25-0001 T0 25-0004 Lighting Plans 56-0005 D-55A Riprap Outlet Protection 26-0001 T0 26-0006 Signal Plans Signal Plans 56-0005	17-0001	Driveway Profiles	55-0001	EC Watershed Map-Site Monitoring Plan
22-0001 TO 22-0002 Drainage Profiles 56-0002 D-24C Temporary Silt Fence J-Hook, Inlet Sediment Traps 23-0001 TO 23-0013 Earthwork Cross Sections 56-0003 D-41 Construction Exit 24-0001 TO 24-0005 Utility Plans 56-0004 D-54 Sod Installation 25-0001 TO 25-0004 Lighting Plans 56-0005 D-55A Riprap Outlet Protection 26-0001 TO 26-0006 Signing and Marking Plans 56-0005 Signal Plans	18-0001 TO 18-0009			
23-0001 TO 23-0013 Earthwork Cross Sections 56-0003 D-41 Construction Exit 24-0001 TO 24-0005 Utility Plans 56-0004 D-54 Sod Installation 25-0001 TO 25-0004 Lighting Plans 56-0005 D-55A Riprap Outlet Protection 26-0001 TO 26-0006 Signing and Marking Plans 56-0005 Signal Plans	19-0001 TO 19-0015	Construction Staging Plans	56-0001	D-24A Temporary Silt Fence
24-0001 TO 24-0005 Utility Plans 56-0004 D-54 Sod Installation 25-0001 TO 25-0004 Lighting Plans 56-0005 D-55A Riprap Outlet Protection 26-0001 TO 26-0006 Signing and Marking Plans Signal Plans 27-0001 TO 27-0002 Signal Plans Signal Plans	22-0001 TO 22-0002	Drainage Profiles	56-0002	D-24C Temporary Silt Fence J-Hook, Inlet Sediment Traps
25-0001 TO 25-0004 Lighting Plans 56-0005 D-55A Riprap Outlet Protection 26-0001 TO 26-0006 Signing and Marking Plans 27-0001 TO 27-0002 Signal Plans	23-0001 TO 23-0013	Earthwork Cross Sections	56-0003	D-41 Construction Exit
26-0001 TO 26-0006 Signing and Marking Plans 27-0001 TO 27-0002 Signal Plans	24-0001 TO 24-0005	Utility Plans	56-0004	D-54 Sod Installation
27-0001 TO 27-0002 Signal Plans	25-0001 TO 25-0004	Lighting Plans	56-0005	D-55A Riprap Outlet Protection
·	26-0001 TO 26-0006	Signing and Marking Plans		
	27-0001 TO 27-0002	Signal Plans		

7/2/2025 Ali.Donnes		11:16:15 AM GPLOT-ORD gplotborder-ORD-PO.tbl		013933005_03.dgn							
	DATE	DRAWING NO. RE	VISION			DATE	DRAWING NO.	REVISION			
			Γ	T				REVISIO	N DATEC I		
					V:1			REVISION		REVISION SUMMA	
					Kimley»Ho)rn				IDLEWOOD RD AT FELLO	WSHIP RD
					Engineering, Planning, And Environmental 0 3930 East Jones Bridge Road, Suite Peachtree Corners, Georgia 3009	Consultants 350 92	NOT TO COME		CHECKED: BACKCHECKED:	DATE: DATE:	DRAWING No.
GPLN-CE							NOT TO SCALE		CORRECTED: VERIFIED:	DATE: DATE:	03-0001

13933005 04.dgn ohn . OBr i en nlotborder-ORD-PO.tbl

- 1. ALL CONSTRUCTION SHALL CONFORM TO THE CURRENT STANDARDS AND SPECIFICATIONS FOR ALL APPROPRIATE JURISDICTIONS.
- 2. ALL CONSTRUCTION OF UTILITIES TO BE SCHEDULED AND APPROVED BY THE OWNER PRIOR TO ANY DISRUPTION OF SERVICES.
- 3. THE CONTRACTOR IS TO VERIFY ALL LOCATIONS AND/OR TYPES OF UTILITIES NEAR THE PROJECT LIMITS BEFORE CONSTRUCTION BEGINS. ANY DAMAGE CAUSED BY THE CONTRACTOR'S PERSONNEL OR EQUIPMENT TO EXISTING UTILITIES SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR TO OWNERS SPECIFICATIONS. SUCH DAMAGE SHALL BE THE CONTRACTORS EXPENSE TO PAY FOR ALL MATERIALS, LABOR, AND NECESSARY PERMITS.
- 4. GRADE TO PROVIDE POSITIVE DRAINAGE AWAY FROM BUILDINGS AND INTO STORM STRUCTURES.
- 5. ALL SURFACE AREAS TO HAVE POSITIVE DRAINAGE AT THE CONCLUSION OF THE CONTRACT.
- 6. TOPS OF ALL EXISTING STRUCTURES THAT ARE TO REMAIN WITHIN THE AREA REQUIRING RE-GRADING SHALL BE RAISED OR LOWERED AS REQUIRED TO MEET NEW GRADES. PRIOR TO ANY ADJUSTMENT THE CONTRACTOR IS TO COORDINATE SUCH WORK WITH THE OWNER. THESE ADJUSTMENTS WILL BE INCLUDED IN THE CONTRACT BID PRICE.
- APPROVED EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY CLEARING, GRADING, OR OTHER LAND DISTURBANCE ACTIVITY AND SHALL BE MAINTAINED IN ACCORDANCE TO CURRENT EDITION OF THE MANUAL OF EROSION AND SEDIMENT CONTROL IN GEORGIA.
- 8. ALL BORROW AND WASTE SITES FOR THIS PROJECT SHALL BE ENVIRONMENTALLY APPROVED PRIOR TO CONSTRUCTION ACTIVITIES OCCURRING IN THEM. ALL COMMON FILL OR EXCESS MATERIAL DISPOSED OUTSIDE THE PROJECT RIGHT OF WAY SHALL BE PLACED IN EITHER A PERMITTED SOLID WASTE FACILITY, A PERMITTED INERT WASTE LANDFILL OR IN AN ENGINEERED FILL. SEE GDOT SECTION 201 OF THE STANDARD SPECIFICATION AND SUPPLEMENTS THERETO FOR ADDITIONAL INFORMATION.
- ALL DRIVEWAYS THAT ARE TO BE RECONSTRUCTED WILL BE PAVED BACK TO THE TIE IN POINT OR EXISTING RIGHT OF WAY, WHICHEVER IS GREATER, ALL DRIVEWAYS OVER 11% IN GRADE SHALL BE PAVED WITH CONCRETE. ALL OTHER DRIVEWAYS SHALL BE REPLACED AS FOLLOWS: ASPHALT FOR ASPHALT, CONCRETE FOR CONCRETE, AND ASPHALT FOR EARTH / GRAVEL DRIVES, RESIDENTIAL DRIVES SHALL BE 14 FEET WIDE AT THE THROAT UNLESS NOTED OTHERWISE IN THE PLANS. COMMERCIAL DRIVES SHALL BE 24 FEET WIDE UNLESS NOTED OTHERWISE IN THE PLANS. EXISTING DRIVEWAY LOCATIONS ARE SHOWN FROM THE BEST AVAILABLE DATA; THE CONTRACTOR SHALL CONSTRUCT DRIVEWAYS TO MATCH THE LOCATION OF EXISTING DRIVEWAYS AT THE TIE IN POINT, IF APPLICABLE, THE CONTRACTOR SHALL OBTAIN THE APPROVAL FROM THE ENGINEER PRIOR TO MAKING ANY REVISIONS TO LOCATION, WIDTH, AND/OR NUMBER OF DRIVES TO BE CONSTRUCTED. DRIVES SHALL BE CONSTRUCTED USING: RESIDENTIAL:

ASPHALT - 165 LB/SY RECYCLED ASPHALT CONC, 12.5 MM SUPERPAVE, GP 2 ONLY,

INCL BITUM MATL & H LIME

- 6" GRADED AGGREGATE BASE CONCRETE - DRIVEWAY CONCRETE, 6 IN THICK COMMERCIAL:

ASPHALT- 165 LB/SY RECYCLED ASPHALT CONC, 12.5 MM SUPERPAVE, GP 2 ONLY,

- INCL BITUM MATL & H LIME
- 220 LB/SY RECYCLED ASPHALT CONC, 19 MM SUPERPAVE, GP 1 OR 2 INCL BITUM MATL & H LIME
- GRADED AGGREGATE BASE, 6" CONCRETE- DRIVEWAY CONCRETE, 8 IN THICK
- 10. THE METHOD OF UTILITY LOCATION IS SUE LEVEL B.
- 11. INGRESS AND EGRESS SHALL BE MAINTAINED AT ALL TIMES TO ADJACENT PROPERTIES.
- 12. THE COST OF REMOVAL OF EACH TEMPORARY DRAINAGE STRUCTURE IS INCLUDED IN THE BID PRICE FOR EACH ITEM. THE CONTRACTOR, WITH APPROVAL FROM THE ENGINEER, MAY ABANDON A TEMPORARY DRAINAGE STRUCTURE IF THE STRUCTURE IS FILLED WITH FLOWABLE FILL, WHICH WILL NOT BE PAID FOR SEPARATELY.
- 13. ALL RAMPS AND SIDEWALKS WITHIN RADII WILL BE CONSTRUCTED IN 8" CONCRETE.
- 14. THE REMOVAL AND RESETTING OF EXISTING SIGNS DURING STAGED CONSTRUCTION TO BE INCLUDED IN THE OVERALL BID PRICE FOR
- 15. POST-CONSTRUCTION STORMWATER BMPS ARE NOT INCLUDED IN THIS PROJECT.
- 16. THE CONTRACTOR IS TO SAWCUT THE EDGES OF PAVEMENT TO PROVIDE SMOOTH EDGES THROUGHOUT THE PROJECT. COST WILL BE INCLUDED IN THE PRICE BID FOR GRADING COMPLETE.
- 17. ALL EXISTING PIPES WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED UNLESS OTHERWISE NOTED ON THE PLANS. THE COST FOR REMOVAL WILL BE INCLUDED IN THE PRICE BID FOR GRADING COMPLETE.

- 18. THE CONTRACTOR SHALL ENSURE THAT NO CONSTRUCTION-RELATED ACTIVITIES (SUCH AS THE USE OF EASEMENTS, STAGING, CONSTRUCTION, VEHICULAR USE, BORROW OR WASTE ACTIVITIES, SEDIMENT BASINS, TRAILER PLACEMENT, ETC.) OCCUR IN THE CRITICAL ROOT ZONE (CRZ) OF EXISTING TREES TO REMAIN IN THE RIGHT OF WAY. THIS DOES NOT APPLY TO THE TREES WITHIN THE CONSTRUCTION LIMITS OR LIMITS OF DISTURBANCE THAT WILL BE REMOVED OR DESTROYED TO ALLOW FOR CONSTRUCTION.
- 19. ANY VERTICAL CONSTRUCTION EQUIPMENT, SUCH AS CRANES, IN EXCESS OF 200 FEET ABOVE ROADWAY ELEVATION MUST BE EVALUATED BY THE FAA. EVALUATION BY FILING OF "NOTICE OF PROPOSED CONSTRUCTION" FAA FORM 7460-1 MUST BE ACCOMPLISHED NOT EARLIER THAN 18 MONTHS AND NOT LATER THAN 120 DAYS PRIOR TO CONSTRUCTION.
- 20. TWO (2) WEEKS PRIOR TO OPENING ROUNDABOUTS, THE CONTRACTOR SHALL INFORM THE TRAVELING PUBLIC OF THE UPCOMING CHANGE USING PORTABLE CHANGEABLE MESSAGE SIGNS, READING ALTERNATIVELY "NEW CONTROL/YIELD AHEAD"
- 21. THE CONTRACTOR SHALL INFORM APPROPRIATE UTILITY COMPANY, IN WRITING, OF THE DATE WHEN THE COST FOR MAINTAINING POWER TO THE LIGHTING OF THE PROJECT IS TO BE TRANSFERRED FROM THE RESPONSIBILITY OF THE CONTRACTOR TO THE GOVERNING PARTY
- 22. ALL CUT AND FILL SLOPES SHALL BE GRASSED AS DIRECTED BY THE ENGINEER IMMEDIATELY AFTER THE SLOPES ARE ESTABLISHED IN ORDER TO REDUCE EROSION. IF THE SEASON DOES NOT PERMIT GRASSING, TEMPORARY MULCH SHALL BE USED AS DIRECTED BY THE ENGINEER. REFER TO SECTION 161 OF THE STANDARD SPECIFICATIONS.
- 23. THE CONTRACTOR SHALL ENSURE THAT POSITIVE AND ADEQUATE DRAINAGE IS MAINTAINED AT ALL TIMES WITHIN THE PROJECT LIMITS. THIS MAY INCLUDE, BUT IS NOT LIMITED TO, REPLACEMENT OR RECONSTRUCTION OF EXISTING DRAINAGE STRUCTURES THAT HAVE BEEN DAMAGED OR REMOVED OR REGRADED AS REQUIRED BY THE ENGINEER EXCEPT FOR THOSE DRAINAGE ITEMS SHOWN AT SPECIFIC LOCATIONS IN THE PLANS AND HAVING SPECIFIC PAY ITEMS IN THE DETAILED ESTIMATE. NO SEPARATE PAYMENT WILL BE MADE FOR ANY COSTS INCURRED TO COMPLY WITH THIS REQUIREMENT.
- 24. ALL SILT FENCES MUST BE PLACED AS ACCESS IS OBTAINED DURING CLEARING. NO GRADING SHALL BE DONE UNTIL SILT FENCE INSTALLATION IS COMPLETE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN ALL SILT FENCES AND TO REPAIR OR REPLACE ANY SILT FENCE THAT IS NOT SATISFACTORY. EROSION CONTROL CHECK DAMS SHALL BE PLACED IMMEDIATELY AFTER DRAINAGE STRUCTURES ARE IN PLACE. ALL EROSION CONTROL DEVICES SHALL BE PLACED ACCORDING TO THE PLANS AND AS DIRECTED BY THE ENGINEER. SEE THE GADOT STANDARD SPECIFICATION REGARDING EROSION CONTROL AND THE MANUAL FOR EROSION AND SEDIMENT CONTROL BY G.S.W.C.C. THE CONTRACTOR SHALL OBTAIN AND ABIDE BY ALL CORPS OF ENGINEERS RULES AND REGULATIONS CONCERNING CONSTRUCTION ADJACENT TO WATERWAYS AND MAINTAIN WATER QUALITY.
- 25. DURING EXCAVATION FOR PROPOSED UTILITIES AND FOUNDATIONS. THE CONTRACTOR SHALL TAKE CARE TO NOT DISTURB ADJACENT EXISTING STRUCTURES AND FOUNDATIONS. IF REQUIRED THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND INSTALLATION OF ANY PROPOSED TEMPORARY SHORING. ANY PROPOSED SHORING SHALL BE SUBMITTED TO THE REQUIRED STAKEHOLDERS FOR REVIEW AND APPROVAL, PRIOR TO INSTALLATION OF TEMPORARY SHORING, CONTRACTOR SHALL DOCUMENT THE CONDITIONS OF THE EXISTING STRUCTURES BEFORE AND AFTER CONSTRUCTION ACTIVITIES TO THE SATISFACTION OF THE STAKEHOLDERS.
- 26. THE CONTRACTOR SHALL FIELD LOCATE SEPTIC SYSTEM ON PARCEL 7 PRIOR TO COMMENCING ANY CONSTRUCTION ACTIVITIES. PAYMENT AND COST FOR THIS WORK TO BE INCLUDED IN COST BID FOR GRADING COMPLETE.
- 27. IF ANY UNDERGROUND UTILITIES ARE DISTURBED ON PARCEL 11 DURING THE PROJECT CONSTRUCTION PERIOD, THEY WILL BE REPAIRED BY THE CITY OF TUCKER'S SELECTED CONTRACTOR AT NO COST TO THE PROPERTY OWNER.
- 28. ALL LANDSCAPING QUANTITIES INCLUDED IN THE PLANS SHALL BE INSTALLED ACCORDING TO GDOT DETAIL RA-1 WITH THE EXCEPTION OF LIRIOPE MUSCARI WHICH SHALL BE INSTALLED AT MAX 1.5-FEET O.C. SPACING INSTEAD OF 3-FEET O.C.



LITY OWNER
LITT OWNER
AT&T
COMCAST
RGIA POWER
ZAYO
TA GAS LIGHT
ALB COUNTY
ALB COUNTY

REVISION DATES GENERAL NOTES IDLEWOOD RD AT SARR PKWY DRAWING No. N.T.S04-0001

13. WHERE SIGNS WITHIN AN ASSEMBLY EXTEND BELOW THE STANDARD MOUNTING HOLES ON THE POST(S), ADDITIONAL 3/8 INCH DIAMETER HOLE(S), DRILLED OR PUNCHED, SHALL BE REQUIRED TO PROPERLY MOUNT THE ASSEMBLY.

REVISION DATES


GENERAL NOTES


IDLEWOOD RD AT SARR PKWY


CHECKED:
BACKCHECKED:
CORRECTED:
DATE:
CORRECTED:
DATE:
D


Kimley» Horn
Engineering, Planning, and Environmental Consultants


N.T.S











NO SCALE

CLASS "B" CONCRETE BASE FOR PAVEMENT WIDENING

Item Code 500-9999 - CY Unit of Measure


Case 1


Where GAB is required under the new Curb and Gutter and the depth of proposed paving between the top of the GAB and the bottom of the surface course is 5 inches or greater, Class B concrete shall be placed in lieu of the paving between the GAB and surface courses specified by the typical section.


Case 2

Where GAB is not required under the new Curb and Gutter and/or the depth of proposed paving between the top of the Base and the bottom of the surface course is less than 5 inches, Class B concrete shall be placed beneath the proposed surface course to the depth of either the bottom of the existing base course, the bottom of the Base specified by the typical section, or to a depth of 6 inches:

CLASS "B" CONCRETE BASE FOR WIDENING DETAIL







Kimley» Horn

Engineering, Planning, And Environmental Consultants
3930 East Jones Bridge Road, Sulte 350

REVISION DATES

TYPICAL SECTIONS

IDLEWOOD RD AT FELLOWSHIP RD

CHECKED:

DATE:

DRAWING NO.

CORRECTED:

DATE:

O5 - 0005

LUMP SUM ITEMS						
ITEM	PAY ITEM	UNIT	QUANTITY			
TRAFFIC CONTROL	150-1000	LS	1			
GRADING COMPLETE	210-0100	LS	1			

PAVING QUANTITIES											
ITEM	PAY ITEM	UNIT	Idlewood Rd N	Idlewood Rd S	Fellowship Rd N	Fellowship Rd S	RT Bypass NW	RT Bypass SE	Circulatory Rdwy	AS DIRECTED (5%)	TOTALS
GR AGGR BASE CRS, INCL MATL	310-1101	TN	153	174	88	155	78	75	383	55	1161
RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	402-1812	TN	71	0	0	0	1	2	3	4	81
RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	402-3121	TN	24	38	13	22	21	18	70	10	216
RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	402-3190	TN	12	19	7	11	11	9	35	5	109
RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 1 OR 2, INCL POLYMER-MODIFIED BITUM MATL & H LIME	402-4510	TN	126	115	74	91	14	16	65	25	526
TACK COAT	413-0750	GL	114	110	67	84	19	19	77	25	515
MILL ASPH CONC PVMT, VARIABLE DEPTH	432-5010	SY	1386	1392	926	715	203	259	240	0	5377
PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	446-1100	LF	27	46	105	142	0	43	137	51	1080
CLASS B CONC	500-3200	CY	5	3	3	6	2	2	1	1	23

PAVING QUANTITIES								
ITEM	PAY ITEM	UNIT	QUANTITY					
RIGHT OF WAY MARKERS	634-1200	EA	31					
PLAIN PC CONC PVMT, CL 3 CONC, 10 INCH THK	439-0022	SY	216					
CONC SIDEWALK, 4 IN	441-0104	SY	722					
CONC SIDEWALK, 8 IN	441-0108	SY	223					
CONCRETE MEDIAN, 7 1/2 INCH	441-0754	SY	975					
CONCRETE HEADER CURB, 4 IN, TP 1	441-5001	LF	107					
CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	441-6222	LF	1,863					
CONC CURB & GUTTER, 8 IN X 32 IN, TP 9	441-6743	LF	195					
CURB CUT WHEELCHAIR RAMP, TYPE A	441-7011	EA	2					
CURB CUT WHEELCHAIR RAMP, TYPE B	441-7012	EA	2					
CURB CUT WHEELCHAIR RAMP, TYPE D	441-7014	EA	3					
RAISED CROSSWALK WITH FLUME	441-9000	EA	10					
DETECTABLE WARNING SURFACE	999-5200	SF	286					
•								

1 4:	T	Olasas	\A/:-III-	Area (Sq	Area (Sq	Area (Sq	VG Area	Driveway Concrete, 6 in Tk	Conc Valley Gutter, 6 in	
Location	Туре	Class	Width	tn Ft)	Ft)	Ft)	Ft) Yd)	(Sq Ft)	SY	SY
							441-0016	441-4020		
102+18	CONCRETE	RESIDENTIAL	14	91.28	10.14	255.03	11	29		
103+40	CONCRETE	RESIDENTIAL	14	243.68	27.08	269.17	28	30		
105+05	CONCRETE	RESIDENTIAL	14	449.91	49.99	386.78	50	43		
201+56	CONCRETE	RESIDENTIAL	14	71.00	7.89	312.78	8	35		
203+04	CONCRETE	RESIDENTIAL	14	305.78	33.98	298.72	34	34		
204+58	CONCRETE	RESIDENTIAL	18	227.93	25.33	271.74	26	31		
205+24	CONCRETE	RESIDENTIAL	14	152.94	16.99	249.61	17	28		
205+98	CONCRETE	RESIDENTIAL	14	83.42	9.27	258.73	10	29		
206+10	CONCRETE	RESIDENTIAL	14	114.57	12.73	252.50	13	29		
206+28	CONCRETE	RESIDENTIAL	18	100.95	11.22	285.24	12	32		
TOTALS							209	320		

	TEMPORARY EROSION CONTROL QUANTITIES								
ITEM	PAY ITEM	UNIT	QUANTITY						
163-0240	MULCH	TN	21						
163-0232	TEMPORARY GRASSING	AC	1						
171-0010	TEMPORARY SILT FENCE, TYPE A	LF	2043						
165-0010	MAINTENANCE OF TEMPORARY SILT FENCE - TP A	LF	2043						
165-0310	MAINTENANCE OF CONSTRUCTION EXIT TIRE WASH AREA (PER EACH)	EA	1						
163-0301	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	EA	1						
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	1						
163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	33						
165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	33						

PERMANENT EROSION CONTROL QUANTITIES							
ITEM	PAY ITEM	UNIT	QUANTITY				
PERMANENT GRASSING	700-6910	AC	1				
AGRICULTURAL LIME	700-7000	TN	2				
FERTILIZER MIXED GRADE	700-8000	TN	1				
FERTILIZER NITROGEN CONTENT	700-8100	LB	44				
SOD	700-9300	SY	772				

LANDSCAPING QUANTITIES							
PAY ITEM	ITEM	UNIT	QUANTITY				
701-0010	WILDFLOWER SEEDING	AC	1				
702-0559	LIRIOPE MUSCARI -	EA	315				
702-0950	RHODODENDRON X ENCORE -	EA	168				
702-0542	CERCIS CANADENSIS - 6' CLEAR TRUNK AT INSTALL	EA	3				
702-9005	SPRING APPLICATION FERTILIZER	LB	1				
702-9025	LANDSCAPE MULCH	SY	96				

	DRAINAGE QUANTITIES								
STRUCTURE NUMBER	LOCATION	ALLOWABLE PIPE 디 MATERIALS (STORM DRAIN)	ADJUST CATCH BASIN TO GRADE	DROP INLET, GA STD, 1019 A TP D	DROP INLET, ADDITIONAL DEPTH, GA STD, 1019 A TP D	DROP INLET, GA STD, 1019 A TP E	RECONST EXIST CATCH BASIN TO MANHOLE	RECONST EXIST DROP INLET TO MANHOLE	CATCH BASIN, GA STD, 1033 D
		18" CLASS III	EA	EA	EA	EA	EA	EA	EA
		550-5180	611-8000	668-2100	668-2110	668-2100	611-3000	611-3010	668-1100
A-1	STA. 105+53.00, 18.30' RT	50	0	1	0	0	0	0	0
A-2	STA. 204+20.46, 20.08' LT	144	0	1	0	0	0	0	0
A-3	STA. 204+24.58, 29.92' RT	48	0	1	0	0	0	0	0
A-4	STA. 103+40.42, 39.43' RT	25	0	0	0	0	0	1	0
A-5	STA. 102+81.17, 30.30' RT	57	0	0	0	0	0	0	1
A-6	STA. 205+34.10, 18.95' RT	96	0	1	0	0	0	0	0
A-7	STA. 103+37.88, 24.81' RT	14	0	1	0	0	0	0	0
A-8	STA. 204+43.69, 17.92' LT	23	0	1	0	0	0	0	0
B-1	STA. 107+12.90, 23.64' LT	0	1	0	0	0	0	0	0
B-2	STA. 106+23.20, 31.07' LT	90	0	0	0	0	0	0	1
B-3	STA. 202+20.27, 38.99' LT	62	0	1	0.77	0	0	0	0
B-EX2	STA. 201+36.21, 20.88' LT	82	1	0	0	0	0	0	0
B-4	STA. 201+52.06, 29.52' RT	52	0	0	0	0	1	0	0
B-5	STA. 201+75.07, 23.49' RT	17	0	0	0	0	0	0	1
B-6	STA. 202+48.57, 18.00' LT	35	0	1	0.8	0	0	0	0
B-7	STA. 202+49.76, 4.34' RT	21	0	1	1.21	0	0	0	0
B-8	STA. 203+07.15, 44.29' RT	70	0	1	0.68	0	0	0	0
B-9	STA. 103+56.00, 22.89' LT	93	0	1	1.61	0	0	0	0
B-10	STA. 103+59.73, 10.41' LT	12	0	1	0.50	0	0	0	0
B-11	STA. 106+07.47, 4.72' LT	30	0	0	0	1	0	0	0
	TOTAL	1021	2	12	6	1	1	1	3

Kim	ley»	Horn

Engineering, Planning, And Environmental Consultants 3930 East Jones Brldge Road, Sulte 350 Peachtree Corners, Georgia 30092

KEVI.	<u> 510N L</u>	IALES	
			l
			l
			CHE

SUMMARY OF QUANTITIES
IDLEWOOD RD AT FELLOWSHIP RD

NOT TO SCALE

06-0001

	,			,	SUMMAR'	OF QUANTIT	IES - STANDAF	RD SIGNS						
										POST			POST	
	INSTL.	SIGN	TP 1 MAT	TL, REFL SHEE	TING TP 9	TP 1 MAT	L, REFL SHEE	TING TP 11	TYPE 7				TYPE 8	
SIAHON	NO.	CODE	SIZE	QUANTITY	SQUARE FEET	SIZE	QUANTITY	SQUARE FEET	LENGTH (FEET)	QUANTITY	TOTAL LENGTH	LENGTH (FEET)	QUANTITY	TOTAL LENGTH
				636-1033			636-1036			636-2070			636-2080	
101+65 RT		W2-6				36X36	1	9			0	14.5	1	14.5
		W13-1P				18X18	1	2.25			0			0
102+36 LT		R3-8	30X30	1	6.25				12.5	1	12.5			0
102+53 RT		R4-7	24X30	1	5				12.5	1	12.5			0
103+01 LT		R3-17	24X18	1	3				11.5	1	11.5			0
103+03 RT		W11-2									0			0
100 - 71 DT		W16-7P				00 TDI	4	4.5	40	,	0			0
103+71 RT		R1-2				36 TRI	1	4.5	13	1	13			0
103+80 RT		R1-2	48X12	1	4	36 TRI	1	4.5	13	1	13			0
103+88 RT 104+23 LT		D1-1d R6-4B	60X24	1	10				11	2	11 24			0
104+23 LT		R6-4B	60X24	1	10				12	2	24			0
104+95 RT		D1-1d	48X12	1	4				11	1	11			0
104+99 LT		R1-2	107112			36 TRI	1	4.5	13	1	13			0
105+12 LT		R1-2				36 TRI	1	4.5	13	1	13			0
105+85 LT		W11-2									0			0
		W16-7P									0			0
106+36 LT		MARTA BUS STOP	24X30	1	5				12.5	1	12.5			0
106+54 RT		R3-17	24X18	1	3				11.5	1	11.5			0
106+81 LT		R3-17	24X18	1	3				12.5	1	12.5			0
		R3-17B	24X9	1	1.5						0			0
107+08 RT		R3-8	48X30	1	10				12.5	1	12.5			0
107+12 LT		R3-8	48X30	1	10				12.5	1	12.5			0
107+39 RT		R4-7	24X30	1	5				12.5	1	12.5			0
107+52 RT		MARTA BUS STOP	24X30	1	5				12.5	1	12.5			0
108+05 RT		R2-1 W2-6	24X30	1	5	36X36	1	9	12.5	1	12.5 0	14.5	1	14.5
108+18 LT		W13-1P				18X18	1	2.25			0	14.5	<u> </u>	0
201+29 RT		W2-6				36X36	1	9			0	14.5	1	14.5
201-20101		W13-1P				18X18	1	2.25			0	14.0	'	0
201+95 RT		R4-7	24X30	1	5	107110		2.20	12.5	1	12.5			0
201+99 LT		R1-2				36 TRI	1	4.5	13	1	13			0
202+22 RT		R3-8	30X30	1	6.25				12.5	1	12.5			0
202+25 LT		R3-8	30X30	1	6.25				12.5	1	12.5			0
202+43LT		R1-2				36 TRI	1	4.5	13	1	13			0
202+92 LT		D1-1d	54X12	1	4.5				11	1	11			0
202+95 RT		R1-2				36 TRI	1	4.5	13	1	13			0
203+03 RT		R1-2				36 TRI	1	4.5	13	1	13			0
203+44 RT		R6-4B	60x24	1	10				12	2	24			0
203+71 LT		R6-4B	60x24	1	10	20. TDI	4	4.5	12	2	24			0
204+14 LT 204+16 LT		R1-2 R1-2				36 TRI 36 TRI	1	4.5 4.5	13 13	1	13 13			0
204+16 LT 204+16 RT		D1-1d	54X12	1	4.5	30 IKI	1	4.0	11	1	13	-	+	0
204+16 RT 204+54 RT		R1-10	J4A12		4.0	36 TRI	1	4.5	13	1	13			0
204+94 RT		R1-2				36 TRI	1	4.5	13	1	13			0
205+06 RT		R4-7	24X30	1	5	00 1101	<u>'</u>	1.0	12.5	1	12.5			0
206+52 LT		W2-6	2.700	'		36X36	1	9	12.0	<u>'</u>	0	14.5	1	14.5
		W13-1P				18X18	1	2.25			0	1	<u> </u>	0
206+69 RT		R2-1	24X30	1	5				12.5	1	12.5			0
TOTAL					147			99			494			58

	LIGHTING QUANTITIES		
PAY ITEM	ITEM	UNIT	QUANTITY
682-2120	PULL BOX, TYPE 2	EA	9
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	959
682-9950	DIRECTIONAL BORE - 3"	LF	523

	SIGNING QUANTITIES (CONT)						
PAY ITEM	ITEM	UNIT	QUANTITY				
610-9001	REM SIGN	EA	1				
611-5551	RESET SIGN	EA	1				
647-1040	FLASHING BEACON INSTALLATION	EA	10				

PAVEMENT MARKING QUANTITIES							
ITEM	PAY ITEM	UNIT	QUANTITY				
THERMOPLASTIC PAVEMENT MARKING, SYMBOL, TP 4	652-0094	EA	3				
THERMOPLASTIC PAVEMENT MARKING, ARROW, TP 1	653-0110	EA	6				
THERMOPLASTIC PAVEMENT MARKING, ARROW, TP 2	653-0120	EA	5				
THERMOPLASTIC PAVEMENT MARKING, ARROW, TP 2A	653-0122	EA	2				
THERMOPLASTIC PAVEMENT MARKING, ARROW, TP 3A	653-0132	EA	4				
THERMOPLASTIC PAVEMENT MARKING, WORD, TP 15	653-0296	EA	8				
THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	653-1704	LF	338				
THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	653-1804	LF	1192				
THERMOPLASTIC SOLID TRAF STRIPE, 6 IN, WHITE	653-1906	LF	1693				
THERMOPLASTIC SOLID TRAF STRIPE, 6 IN, YELLOW	653-2602	LF	1414				
THERMOPLASTIC SKIP TRAF STRIPE, 6 IN, WHITE	653-2611	GLF	572				
THERMOPLASTIC SKIP TRAF STRIPE, 18 IN, WHITE	653-4830	GLF	173				
THERMOPLASTIC TRAF STRIPING, WHITE	653-6004	SY	83				
THERMOPLASTIC TRAF STRIPING, YELLOW	653-6006	SY	648				
RAISED PVMT MARKERS TP 1	654-1001	EA	56				
REMOVE EXIST SOLID TRAF STRIPE, 5 IN, THERMOPLASTIC	656-0050	LF	462				

Kimley >>> Horn
Engineering. Planning. And Environmental Consultants


Engineering, Planning, And Environmental Consultants 3930 East Jones Brldge Road, Sulte 350 Peachtree Corners, Georgia 30092 REVISION DATES


NOT TO SCALE


SUMMARY OF QUANTITIES
IDLEWOOD RD AT FELLOWSHIP RD


CHECKED: DATE: DRAWING NO.


BACKCHECKED: DATE:
CORRECTED: DATE:
VERIFIED: DATE:
DATE:















































13933005 18.dgr li.Donnes olothorder-ORD-PO.thi Northing Easting Elevation Alignment Station Offset Station Offset Northing Point Alianment Easting Elevation Point Alignment Station Offset Northing Easting Elevation 1397783.22 2282401 IDELWOOD RD | 102+43.487 | -20.12 | 1397520.458 2282400 286 1087 446 IDELWOOD RD | 105+06.740 | -38.81 1085.073 FELLOWSHIP RD 202+92.125 36.85 1397737.578 2282349.513 1085.65 C2 IDELWOOD RD 105+16.867 1397791.278 2282404 1084.923 IDELWOOD RD 102+63.541 -19.37 1397539.766 2282399.05 1087.301 -36.16 B2 FELLOWSHIP RD 202+71.550 32.03 1397756.445 | 2282339.998 1085.867 СЗ IDELWOOD RD 105+26.956 -33.84 1397799.58 2282406 1084.772 IDELWOOD RD | 102+83.434 | -18.77 | 1397559.003 | 2282396.978 1087.155 IDELWOOD RD 105+49.497 -31.31 397819.589 2282407 Α4 IDELWOOD RD | 103+02.812 | -17.44 | 1397578.36 | 2282395.388 1087 01 В3 FELLOWSHIP RD 202+51.554 31.44 1397772.155 2282327.613 1086.072 1084.433 IDELWOOD RD 105+68.936 -31.46 1397838.922 2282405 1084.225 IDELWOOD RD | 103+22.373 | -15.64 | 1397597.972 | 2282394.249 B4 FELLOWSHIP RD 202+35.152 1086.858 31.32 1397784.808 2282317.175 1086.24 C6 IDELWOOD RD | 106+08.941 | -30.92 1397878.79 2282402 1083.788 IDELWOOD RD | 103+40.707 | -17.78 | 1397616.946 2282389.657 B5 FELLOWSHIP RD 202+21.707 1397795.180 2282308.620 31.22 1086.378 IDELWOOD RD 106+28.962 -28.22 1397898.979 2282403 1083.351 IDELWOOD RD | 103+57.578 | -22.24 | 1397635.282 2282384.377 1086.381 В6 FELLOWSHIP RD 202+01.736 1397813.048 2282298.850 27.25 1086.562 C8 IDELWOOD RD 106+48.985 -25.37 1397919.183 2282404 1083.051 IDELWOOD RD | 103+74.147 | -29.34 | 1397654.243 | 2282378.013 1086.12 В7 FELLOWSHIP RD 201+85.348 1397827.900 2282291.062 23.68 1086.76 IDELWOOD RD | 106+69.109 | -23.5 1397939.833 2282404 1082.893 IDELWOOD RD | 103+82.099 | -33.87 | 1397663.858 | 2282374.422 1085.985 Α9 В8 FELLOWSHIP RD 203+01.081 1397746.379 2282373.978 12.44 1085.517 C10 IDELWOOD RD | 106+88.961 | -23.46 A10 | IDELWOOD RD | 102+42.845 | -5.14 | 1397521.092 | 2282415.273 | 1087.668 1397960.496 2282402 1082.769 1397764.503 2282365.582 В9 FELLOWSHIP RD 202+81.795 7.24 1085.617 IDELWOOD RD 107+08.741 -21.88 C11 1397981 123 2282403 1082 646 A11 | IDELWOOD RD | 102+63.005 | -4.38 | 1397541.049 | 2282413.995 | 1087.347 1397773.055 2282360.134 B10 FELLOWSHIP RD 202+71.740 5.93 1085.668 C12 IDELWOOD RD 107+28.468 -21.19 398001.121 2282404 1082.507 IDELWOOD RD | 102+83.118 | -3.77 1397560.933 | 2282411.853 | 1087.197 1397788.700 2282347.670 B11 FELLOWSHIP RD 202+51.743 5.44 1085.768 IDELWOOD RD | 107+48.468 | -21.21 398021.121 2282404 1082.304 A13 | IDELWOOD RD | 103+03.117 | -3.78 1397580.704 2282408.851 1087.001 1397811.725 2282328.677 B12 FELLOWSHIP RD 202+21.896 5.23 1086.02 IDELWOOD RD 104+95.986 -14.95 1397771.323 2282423 1084.985 A14 | IDELWOOD RD | 103+23.096 | -4.66 | 1397600.327 | 2282404.994 1086.774 B13 FELLOWSHIP RD 202+01.897 1397827.153 2282315.950 1086.333 5 08 IDELWOOD RD 105+08.331 -11.27 1397782.396 2282428 C15 1084 733 A15 | IDELWOOD RD | 103+42.529 | -6.95 | 1397619.764 | 2282400.289 1086.547 B14 FELLOWSHIP RD 201+85.484 4 96 1397839.815 2282305.506 1086.579 C16 IDELWOOD RD 105+23.263 -7.96 1397796.468 2282432 1084.514 A16 | IDELWOOD RD | 103+60.947 | -11.85 | 1397638.876 | 2282394.778 B15 FELLOWSHIP RD 202+95.122 -12.08 1397766.687 2282388.952 1085.099 C17 IDELWOOD RD 105+43.806 -5.47 397816.432 2282434 1084.213 A17 | IDELWOOD RD | 103+78.174 | -19.31 | 1397657.836 | 2282388.411 1086.095 FELLOWSHIP RD 202+84.705 1397772.586 2282379.771 C18 IDELWOOD RD | 105+69.134 | -5.46 1397841.642 2282431 1083.955 A18 IDELWOOD RD 103+86.707 -24.22 1397667.824 2282384.683 1085.974 R16 -8.83 1085.195 C19 IDELWOOD RD | 105+89.134 | -5.61 A19 IDELWOOD RD 102+42.845 6.00 1397522.02 2282426.365 1087.44 B17 FELLOWSHIP RD 202+71.112 -5.97 1397781.174 2282368.853 1085.317 1397861.532 2282429 1083.856 IDELWOOD RD 106+09.133 -5.76 C20 1397881.422 2282427 1083 758 A20 | IDELWOOD RD | 102+62.624 | 6.26 1397541.942 2282424.605 1087.364 B18 FELLOWSHIP RD 202+51.137 -4.43 1397795.505 2282354.853 1085.495 C21 IDELWOOD RD 106+29.133 -5.92 1397901.312 2282425 1083.633 IDELWOOD RD 102+82.411 6.97 1397561.839 2282422.578 A21 1087.257 B19 FELLOWSHIP RD 202+25.098 -5.14 1397815.924 2282338.680 1085.817 IDELWOOD RD 106+49.132 -6.07 1397921.203 2282423 1083.458 IDELWOOD RD 103+02.395 7.78 1397581.719 2282420.395 1087.085 FELLOWSHIP RD 202+05.114 1397831.562 2282326.228 1086.15 B20 -5 63 C23 IDELWOOD RD | 106+69.021 | -6.07 1397941.116 2282421 1083.258 A23 IDELWOOD RD 103+22.378 8.60 2282418.212 1086.84 1397601.6 FELLOWSHIP RD 201+85.484 -1.80 1397844.156 2282310.691 1086.5 B21 C24 IDELWOOD RD 106+88.804 -5.93 1397961.086 2282420 1083.058 A24 IDELWOOD RD 103+44.931 8.81 1397623.279 2282415.831 1086 556 FELLOWSHIP RD 202+89.092 1397782.093 2282397.960 B22 -28.88 1084 702 C25 IDELWOOD RD 107+08.593 -5.7 1397981.083 2282420 1082.858 A25 | IDELWOOD RD | 103+66.161 | 10.22 | 1397643.506 2282416.987 1086.291 B23 FELLOWSHIP RD 202+80.394 -24.99 1397786.264 2282389.393 1084.821 IDELWOOD RD 107+28.520 -5.72 C26 398001.083 2282420 1082.658 A26 | IDELWOOD RD | 103+82.963 | 14.96 | 1397658.802 | 2282423.003 1086.078 B24 FELLOWSHIP RD 202+69.210 -21 09 1397792.338 | 2282379.226 1085.043 C27 IDELWOOD RD 107+48.520 -5.79 398021.082 2282420 1082.459 IDELWOOD RD | 102+42.821 | 18.01 | 1397522.997 2282438.345 1087,188 B25 FELLOWSHIP RD 202+49.586 1397804.732 2282363.460 -16 96 1085.272 C28 IDELWOOD RD | 104+86.217 | 15.01 1397756.835 2282451 1084.804 A28 IDELWOOD RD 102+62.332 18.54 1397543.105 2282436.836 1087 087 FELLOWSHIP RD 202+02.937 -16.79 1397840.396 2282333.388 1085.862 B26 IDELWOOD RD 105+04.410 9.81 C29 1397776.689 2282449 1084.383 A29 IDELWOOD RD 103+21.801 22.79 1397603.15 2282432.33 1086,686 B27 FELLOWSHIP RD 201+82.443 -17.39 1397856.494 2282320.692 1086.246 C30 IDELWOOD RD 105+23.360 6.43 1397796.543 2282447 1084.081 A30 IDELWOOD RD | 103+39.981 | 23.74 | 1397619.912 | 2282431.073 1086.483 IDELWOOD RD 105+42.761 4.96 1397816.397 2282444 1083.927 A31 | IDELWOOD RD | 103+63.141 | 24.97 | 1397640.269 | 2282431.636 | 1086.177 C32 IDELWOOD RD | 105+62.749 | 4.48 1397836.251 2282442 1083.827 A32 | IDELWOOD RD | 103+76.262 | 28.73 | 1397651.39 | 2282436.043 | 1085.988 1397856.107 2282439 IDELWOOD RD 105+82.743 4.03 1083 727 C34 IDELWOOD RD 106+02.743 3.92 1397876.002 2282437 1083.592 IDELWOOD RD | 106+22.739 | 4.26 397895.937 2282436 1083.442 C36 IDELWOOD RD | 106+42.724 | 5.04 1397915.902 2282434 1083.292 C37 IDELWOOD RD | 106+62.728 | 6.25 1397935.889 2282434 1083.142 C38 IDELWOOD RD 106+82.951 7.29 1397955 885 2282433 1082 992 IDELWOOD RD 107+03.225 7.62 397975.882 2282433 1082.842 IDELWOOD RD | 107+23.392 | 7.26 1397995.878 2282433 1082.692 C41 IDELWOOD RD | 107+48.520 | 6.63 398021.01 2282432 1082.456 IDELWOOD RD 104+89.585 27.06 1397758.358 2282464 C42 1084 556 C43 IDELWOOD RD 105+06.823 21.98 1397778.191 2282461 1084.329 IDELWOOD RD 105+24.729 C44 18.62 397798.024 2282459 1084.058 C45 IDELWOOD RD 105+43.044 17.05 1397817.857 2282456 1083.708 C46 IDELWOOD RD | 105+63.035 | 16.5 1397837.702 2282454 1083.479 C47 IDELWOOD RD 106+22.323 19.17 1397896.969 2282451 1083.292 IDELWOOD RD 106+41.936 20.74 1397916.642 2282450 1083.188 IDELWOOD RD | 106+61.637 | 22.2 1397936.286 2282450 1083 106 C50 IDELWOOD RD | 106+82.375 | 23.29 1397956.191 2282449 1082.994 C51 IDELWOOD RD 107+03.264 23.62 1397976.187 2282449 1082.795 C52 IDELWOOD RD 107+23.791 23.26 1397996.183 2282449 1082.545 IDELWOOD RD 107+48.920 22.64 1398021.315 2282448 1082.307 REVISION DATES SPECIAL GRADING IDLEWOOD RD AT FELLOWSHIP RD **Kimley** » Horn DRAWING No Suite 350, 3930 East Jones Bridge Road Peachtree Corners, Georgia 30092

7/2/2025 Ali.Donnes 013933005_18.dgn

Point	Alignment	Station	Offset	Northing	Easting	Elevation
D1	FELLOWSHIP RD	205+16.952	18.74	1397594.57	2282526	1085.486
D2	FELLOWSHIP RD	204+95.781	20.33	1397607.261	2282512	1085.584
D3	FELLOWSHIP RD	204+75.439	21.28	1397619.028	2282496	1085.682
D4	FELLOWSHIP RD	204+56.407	23.08	1397629.83	2282481	1085.779
D5	FELLOWSHIP RD	204+45.311	24.68	1397635.705	2282471	1085.844
D6	FELLOWSHIP RD	204+25.685	28.53	1397645.314	2282454	1085.994
D7	FELLOWSHIP RD	204+11.160	32.25	1397651.764	2282440	1086.114
D8	FELLOWSHIP RD	205+15.780	5.53	1397604.045	2282535	1086.093
D9	FELLOWSHIP RD	204+95.179	6.73	1397617.57	2282520	1085.913
D10	FELLOWSHIP RD	204+74.799	7.33	1397630.149	2282505	1085.973
D11	FELLOWSHIP RD	204+54.862	8.87	1397641.732	2282489	1086.034
D12	FELLOWSHIP RD	204+42.558	10.44	1397648.411	2282478	1086.048
D13	FELLOWSHIP RD	204+22.914	14	1397658.255	2282461	1085.987
D14	FELLOWSHIP RD	204+07.303	17.73	1397665.385	2282446	1085.938
D15	FELLOWSHIP RD	205+15.780	-4.46	1397610.61	2282543	1085.972
D16	FELLOWSHIP RD	204+96.225	-4.69	1397625.189	2282529	1086.025
D17	FELLOWSHIP RD	204+76.538	-5.36	1397638.783	2282514	1085.945
D18	FELLOWSHIP RD	204+56.541	-5.16	1397651.433	2282499	1085.865
D19	FELLOWSHIP RD	204+41.500	-4.84	1397660.822	2282487	1085.805
D20	FELLOWSHIP RD	204+21.539	-6.09	1397674.564	2282473	1085.725
D21	FELLOWSHIP RD	204+06.001	-9.66	1397687.257	2282463	1085.559
D22	FELLOWSHIP RD	205+15.751	-16.46	1397618.514	2282552	1085.913
D23	FELLOWSHIP RD	204+96.510	-16.69	1397633.701	2282538	1085.943
D24	FELLOWSHIP RD	205+15.751	-16.46	1397618.514	2282552	1085.913
D25	FELLOWSHIP RD	204+56.289	-17.15	1397660.81	2282506	1085.686
D26	FELLOWSHIP RD	204+42.251	-16.86	1397669.573	2282495	1085.595
D27	FELLOWSHIP RD	204+22.314	-18.5	1397683.601	2282481	1085.463
D28	FELLOWSHIP RD	204+10.095	-22.97	1397694.857	2282475	1085.378
D29	FELLOWSHIP RD	204+76.753	-17.36	1397647.861	2282522	1085.82


Point	Alignment	Station	Offset	Northing	Easting	Elevation
E1	CIRCULATORY ROADWAY	301+46.078	18.24	1397673.036	2282393	1085.933
E2	CIRCULATORY ROADWAY	301+36.078	32.63	1397676.059	2282370	1085.926
E3	CIRCULATORY ROADWAY	301+26.078	30.98	1397695.395	2282362	1085.838
E4	CIRCULATORY ROADWAY	30116.078	34.72	1397715.901	2282356	1085.747
E5	CIRCULATORY ROADWAY	300+96.078	28.31	1397750.949	2282377	1085.465
E6	CIRCULATORY ROADWAY	300+86.078	29.34	1397759.04	2282383	1085.28
E7	CIRCULATORY ROADWAY	300+66.078	22.48	1397770.349	2282426	1084.968
E8	CIRCULATORY ROADWAY	300+56.078	21.80	1397764.082	2282440	1084.868
E9	CIRCULATORY ROADWAY	300+36.078	25.28	1397744.441	2282466	1084.786
E10	CIRCULATORY ROADWAY	300+26.078	20.54	1397727.921	2282468	1085.009
E11	CIRCULATORY ROADWAY	300+16.078	20.23	1397712.48	2282470	1085.206
E12	CIRCULATORY ROADWAY	301+86.078	20.67	1397675.099	2282454	1085.764
E13	CIRCULATORY ROADWAY	301+56.078	19.87	1397664.546	2282407	1086.039
E14	CIRCULATORY ROADWAY	301+46.078	2.00	1397686.312	2282402	1085.899
E15	CIRCULATORY ROADWAY	301+36.078	2.00	1397693.809	2282394	1085.736
E16	CIRCULATORY ROADWAY	301+26.078	2.00	1397703.384	2282390	1085.645
E17	CIRCULATORY ROADWAY	301+16.078	2.00	1397713.947	2282389	1085.618
E18	CIRCULATORY ROADWAY	301+06.078	2.00	1397724.296	2282391	1085.555
E19	CIRCULATORY ROADWAY	300+96.078	2.00	1397733.253	2282397	1085.462
E20	CIRCULATORY ROADWAY	300+86.078	2.00	1397740.653	2282404	1085.366
E21	CIRCULATORY ROADWAY	300+72.394	2.00	1397750.782	2282413	1085.235
E22	CIRCULATORY ROADWAY	300+66.078	2.00	1397750.429	2282421	1085.19
E23	CIRCULATORY ROADWAY	300+56.078	2.00	1397746.674	2282431	1085.152
E24	CIRCULATORY ROADWAY	300+46.078	2.00	1397740.5	2282439	1085.145
E25	CIRCULATORY ROADWAY	300+36.078	2.00	1397732.33	2282446	1085.169
E26	CIRCULATORY ROADWAY	300+26.078	2.00	1397722.728	2282450	1085.253
E27	CIRCULATORY ROADWAY	300+16.078	2.00	1397712.329	2282452	1085.395
E28	CIRCULATORY ROADWAY	300+06.078	2.00	1397701.839	2282450	1085.564
E29	CIRCULATORY ROADWAY	301+86.078	2.00	1397688.854	2282441	1085.795
E30	CIRCULATORY ROADWAY	301+76.078	2.00	1397683.094	2282432	1085.945
E31	CIRCULATORY ROADWAY	301+66.078	2.00	1397680.631	2282422	1086.013
E32	CIRCULATORY ROADWAY	301+56.078	2.00	1397681.746	2282412	1086
E33	CIRCULATORY ROADWAY	301+46.078	-12.50	1397698.167	2282410	1086.203
E34	CIRCULATORY ROADWAY	301+26.078	-12.50	1397707.381	2282404	1086.056
E35	CIRCULATORY ROADWAY	301+06.078	-12.50	1397718.666	2282404	1085.886
E36	CIRCULATORY ROADWAY	300+86.078	-15.75	1397728.713	2282417	1085.688
E37	CIRCULATORY ROADWAY	300+46.078	-15.77	1397727.629	2282427	1085.608
E38	CIRCULATORY ROADWAY	300+26.078	-12.81	1397718.581	2282436	1085.672
E39	CIRCULATORY ROADWAY	300+06.078	-12.50	1397706.547	2282436	1085.913
E40	CIRCULATORY ROADWAY	301+76.078	-12.50	1397696.43	2282427	1086.203


Point	Alignment	Station	Offset	Northing	Easting	Elevation
- 1	IDELWOOD RD	102+74.169	24.28	1397556.042	2282440.929	1086.962
-2	IDELWOOD RD	102+91.004	34.54	1397574.457	2282448.555	1086.725
=3	FELLOWSHIP RD	103+04.479	49.23	1397589.976	2282461.062	1086.426
- 4	FELLOWSHIP RD	204+72.518	47.16	1397601.018	2282477.665	1086.118
- 5	FELLOWSHIP RD	204+85.918	32.05	1397604.244	2282497.382	1085.817
-6	IDELWOOD RD	103+17.946	40.03	1397601.916	2282449.948	1086.372
- 7	FELLOWSHIP RD	204+56.361	38.23	1397618.225	2282470.976	1085.915
-8	FELLOWSHIP RD	202+42.223	-38.46	1397824.184	2282375.224	1084.978
- 9	IDELWOOD RD	105+69.506	-38.11	1397838.845	2282398.656	1084.29
=10	FELLOWSHIP RD	201+96.067	-21.11	1397848.434	2282332.288	1085.901
- 11	FELLOWSHIP RD	202+13.602	-30.51	1397841.024	2282350.753	1085.441
-12	FELLOWSHIP RD	202+25.771	-46.17	1397841.748	2282370.575	1084.981
- 13	IDELWOOD RD	105+82.570	-47.39	1397850.945	2282388.144	1084.521
- 14	IDELWOOD RD	105+97.673	-34.6	1397867.218	2282399.41	1084.061


SPECIAL GRADING


DRAWING No.


18-0004











Engineering, Planning, and Environmental Consultants Suite 350, 3930 East Jones Bridge Road Peachtree Corners, Georgia 30092

SCALE IN FEET

DRAWING No.

19-0001

& MAINTENANCE OF SLOPES

EASEMENT FOR CONSTR OF SLOPES

EASEMENT FOR CONSTR OF DRIVES


EXISTING LIMIT OF ACCESS & R/W


ORANGE BARRIER FENCE


XXXX


REQ'D LIMIT OF ACCESS & R/W


ESA - ENV. SENSITIVE AREA



















































































- CONTRACTOR SHALL BE AWARE OF OVERHEAD POWER LINES DURING CONSTRUCTION.
- 3. CONDUIT ACCESSORIES SUCH AS EXPANSION JOINTS, ELBOWS, LB'S, FLEXIBLE CONDUIT, ETC. SHALL BE INCLUDED IN THE PRICE BID FOR CONDUIT.
- 4. LUMINAIRE MUST MEET ALL REQUIREMENTS OUTLINED WITHIN THE GDOT SPECIFICATION 927-LUMINAIRES, LED. ACCORDINGLY, LUMINAIRE MANUFACTURER SHALL PROVIDE A TEN YEAR WARRANTY FOR PARTS AND DEFECTIVE WORKMANSHIP ON LUMINAIRES.
- 5. ALL PITS USED FOR INSTALLED PUSHED (JACKED) CASINGS UNDER EXISTING ROADWAYS SHALL HAVE A MINIMUM OF FIVE FEET BETWEEN EDGE OF SHOULDER. LOCATIONS AS SHOWN ARE APPROXIMATE AND MAY BE SHIFTED AS NECESSARY TO MEET CLEARANCE REQUIREMENTS.
- 6. ALL ELECTRICAL CONNECTIONS SHALL BE MADE ABOVE GRADE INSIDE POLE BASES OR JUNCTION BOXES. NO UNDERGROUND SPLICING ALLOWED.
- CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UTILITIES PRIOR TO INSTALLATION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST.
- 8. THE CONTRACTOR SHALL PROVIDE THE SERVICE POLE UNLESS OTHERWISE NOTED. THE SERVICE RISER AND LATERAL, WEATHERHEAD, WATERPROOF ENCLOSURES, CIRCUIT BREAKERS, LIGHTING ARRESTER, AND THE NECESSARY WIRING FOR CONNECTING TO THE POWER SOURCE, SHALL BE INCLUDED UNDER THE "ELECTRICAL SERVICE POINT" PAY ITEM.
- 9. PRIOR TO INSTALLATION, THE CONTRACTOR SHALL SUPPLY THE FOUNDATION DESIGNS IN ACCORDANCE WITH GEORGIA DOT SPECIFICATIONS FOR ALL FOUNDATIONS ON THE PROJECT. ALL FOUNDATION DESIGNS SHALL BE APPROVED BY THE ENGINEER BEFORE ORDERING FOUNDATION MATERIALS AND INSTALLATION. THE FOUNDATION DESGINS SHALL BE COMPLETED AND STAMPED BY A REGISTERED STRUCTURAL ENGINEER IN THE STATE OF GEORGIA.
- 10.LUMINAIRES SHALL BE FURNISHED WITH CUT-OFF OPTICS AND HOUSE SHIELDS AS PER GDOT SPECIFICATIONS.
- 11.ALL LIGHT STANDARDS SHALL HAVE AN AASHTO APPROVED BREAKAWAY BASE.

POLE	STA. NO.	OFFSET	CENTER/BASE LINE	SHEET NO.	F I XTURE MOUNT I NG HE I GHT	NO. OF LUM'S	INSTALLAITON NOTES
P 1	102+36.34	32.35' RT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P2	102+88.09	52.80' RT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
Р3	103+27.72	36.14' RT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P4	103+56.15	36.58' RT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P 5	103+80.42	48.96' LT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
Р6	202+51.12	43.94' LT	FELLOWSHIP ROAD (DE200)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P7	105+54.31	46.86' LT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P8	106+99.33	50.75' LT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P9	106+45.14	34.36' RT	IDLEWOOD ROAD (DE100)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P10	201+70.96	36.66' RT	FELLOWSHIP ROAD (DE200)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P11	202+51.12	43.94' RT	FELLOWSHIP ROAD (DE200)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P12	203+71.93	36.74' RT	FELLOWSHIP ROAD (DE200)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P13	204+14.44	35.94' LT	FELLOWSHIP ROAD (DE200)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER
P14	204+91.85	28.45' LT	FELLOWSHIP ROAD (DE200)	25-0002	30'	1	TO BE INSTALLED BY GEORGIA POWER

WITH LED LUMINAIRE. (TO BE INSTALLED BY GEORGIA POWER)

PROPOSED ELECTRICAL PULL BOX, TYPE 2

PROPOSED CONDUIT, DIRECTIONAL BORE

PROPOSED CONDUIT

SERVICE POLE WITH TRANSFORMER


CONDUIT AND CABLE SCHEDULE

(NOTE: ALL CONDUCTORS TO BE ALUMINUM UNLESS OTHERWISE SPECIFIED)

- (1) 2" SCHEDULE 40 PVC CONDUIT IN TRENCH
- 2" SCHEDULE 80 PVC CONDUIT IN TRENCH, DIRECTIONAL BORE

LIGHTING QUANTITIES								
PAY ITEM NU	DESCRIPTION	UNIT	QUANTITY					
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	959					
682-2120	PULL BOX, TYPE 2	EA	9					
682-9950	DIRECTIONAL BORE - 3"	LF	523					

Kimley»Horn		REVI	SION D	PATES	IL	LIGHTING IDLEWOOD RD AT FELLOWSHIP RD				
Engineering, Planning, and Environmental Consultants	SCALE IN FEET				CHECKED:		DATE:	DRAWING No.		
Suite 350, 3930 East Jones Bridge Road Peachtree Corners, Georgia 30092					BACKCHECKED: CORRECTED:		DATE:	25 0001		
reachage comers, acorgia 30002	0 20 40 80				VERIFIED:		DATE:	25-0001		







RoadFocus LED Cobra head luminaires feature a sleek design that provides seamless replacement of existing HID luminaires. RoadFocus is available in three sizes offering multiple lumen packages and a complete array of optical distributions, making it an outstanding solution for all types of roadway applications. Includes Service Tag, an innovative way to provide assistance throughout the life of the product.

APPLICATIONS

Roadway lighting, area lighting, pathway lighting

LIGHT SOURCE

LED

COLOR TEMPERATURE

3,000 CCT or 4,000 CCT

WARM-UP AND RESTRIKE TIME

Instant-on (no warm-up or restrike time)

POLES AVAILABLE

Round Tapered Aluminum, Square Straight Steel, Wood

MOUNTING HEIGHT

30' standard (other mounting heights available)

COLORS

Bronze and Grey standard

LIGHT FIXTURE DETAIL:



Road Focus

Mounting Height: 30' standard Colors: Bronze, Grey standard Material: Die-cast aluminum Top Applications: Roadways

POLE DETAIL:



Round Tapered Aluminum

Mounting Height: 30' standard

Colors: Bronze standard


Material: Aluminum


Pole Shaft Style: Round tapered Installation: Direct embed or base


mounted


Kimley »Horn


 _			CHECKED ·		DATE -		DD AW I M	- N
				'DLEWOOD F	RD AT	FELLO	WSHIP RE)
REV I	SION L	DATES			L I GHT	LINC		
REV I	SION L	DATES			1.1.611	- INC		-





























7/1/2025 4:27:40 F Logan.Bennett	M GPLOT-ORD aplotborder-ORD-PO.tbl	013933005_51.dgn							
Logan. bennet t	gprocoorder-okb-PO.Cor								
		EROSION, SEDIMENTATIO	N & POLLUTION CO	NTROL PLAN	N CHECKLIST				
			URE CONSTRUCTIO	N PROJECTS					
	Project Name:		ddress: Idlev	ood Rd at Fe	ellowship Rd, Tucker, GA				
	Local Issuing Authority:		ate on Plans:	7/3/2025	County:	Dekalb			
	Name & email of person		Da Plan	rren Wilton; (darren.wilton@kimley-horn.com				
	Page # Y/N	TO BE SHOWN ON ES&PC PLAN n and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in v	Page #	Y/N	TO BE SHOW rovide complete requirements of <u>Inspections</u> and record keeping b	IN ON ES&PC PLAN by the Primary Permittee. *			
	the land-disturbing activity was permith The completed Checklist <u>must</u> be sub	ed. mitted with the ES&PC Plan or the Plan will not be reviewed. Permit IV.D.1. pg 28	51-0006/51-0007	==	rovide complete requirements of <u>Sampling Frequency</u> and <u>Reporting</u>				
		the Commission, signature and seal of the certified design professional. ust be on each sheet pertaining to ES&PC Plan or the Plan will not be reviewed. The Level II certific:	51-0007 ion 51-0008		rovide complete details for <u>Retention of Records</u> as per Part IV.F. or escription of analytical methods to be used to collect and analyze t				
		ional, after completion of a GSWCC approved course, and whose signature and seal are on the Plan	51-0008		ppendix B rationale for NTU values at all outfall sampling points whe				
		4-hour contact responsible for erosion, sedimentation and pollution controls.	51-0008		elineate all sampling locations on all phases of the Plan, and peren discharged. *	nial and intermittent streams and other water bodies	into which storm water		
	50-0001 Yes 4 Provide the name, address, email address. Find the name address and address are set of the name address and address are set of the name address.	dress, and phone number of Primary Permittee. he project or phase under construction.	51-0005	requ	description of appropriate controls and measures that will be imple quirements and perimeter control BMPs, (2) intermediate grading a	and drainage BMPs, and (3) final BMPs. For construc	tion sites where there		
1	50-0001 Yes 6 Provide the GPS locations of the begi	nning and end of the infrastructure project. Give the Latitudes and Longitudes in decimal degrees.	50 0004	BMF	ill be no mass grading and the initial sediment storage requirement MPs, and final BMPs are the same, the Plan may combine all of the raphic scale and North arrow.		ading and drainage		
	50-0001 Yes 7 Initial date of the Plan and the dates of 51-0002 Yes 8 Descriptions of the nature of constructions.	any revisions made to the Plan including the entity who requested the revisions. on activity and existing site conditions.	50-0001 53-0001 54 Series	Yes Yes	יסטווט מווע זיסיפו מווטיד.				
	50-0001 Yes 9 Provide vicinity map showing site's re	lation to surrounding areas. Include designation of specific phase, if necessary.	55-0001		xisting and proposed contour lines with contour lines drawn at an in	terval in accordance with the following:			
	51-0008 Yes 10 Identify the project receiving waters ar	nd describe all sensitive adjacent areas including streams, lakes, residential areas, wetlands, marshli	nds, 53-0001 55-0001	Yes	Existing Contours USGS 1": 2000' Topographica Proposed Contours 1" : 400' Centerline Prof	l Sheets			
	50-0001 Yes 11 Design professional's certification state page 20 of the permit.	ement and signature that the site was visited prior to development of the ES&PC Plan as stated on P	rt IV 51-0007		se of Alternative BMPs whose performance has been documented esign Professional (unless disapproved by GAEPD or the Georgia				
		ement and signature that the Permittee's ES&PC Plan provides for an appropriate and comprehensiv et permit requirements as stated on Part IV page 20 of the permit. *		Guid	uidance Document found at www.gaswcc.georgia.gov.				
	50-0001 Yes 13 Design professional certification stater Part IV. D.6.c. (3). page 37 of the permi	ment and signature that the Permittee's ES&PC Plan provides for representative sampling as stated o t as applicable. *		Geo	se of Alternative BMP for application to the Equivalent BMP List. Re eorgia 2016 Edition. *				
		esign professional who prepared the ES&PC Plan is to inspect and certify the installation of the initial erimeter control BMPs within 7 days after installation." *			elineation of the applicable 25-foot or 50-foot undisturbed buffers ac suing Authority. Clearly note and delineate all areas of impact.	ljacent to State Waters and any additional buffers as	required by the Local		
	51-0007 Yes 15 Clearly note the statement that "Non-e)	xempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffers as measun r within 25-feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line		Yes 42 Deli	elineation of all State Waters and wetlands located on or within 200	feet of the project site.			
	without first acquiring the necessary va	ariances and permits."	53-0001	Yes 43 Deli	elineation and acreage of contributing drainage basins on the proje	ct site.			
	51-0002 Yes 17 Clearly note the statement that "Amend	croachments and indicate whether a buffer variance is required. dments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic compon	53-0001 ent 55-0001	Yes 44 Deli	elineate on-site drainage and off-site watersheds using USGS 1":20	000' topographical sheets.			
	must be certified by the design profes	isional." * materials shall not be discharged to waters of the State, except as authorized by a Section 404 perm	53-0001 t" * 53-0001		n estimate of the runoff coefficient or peak discharge flow of the site torm-drain pipe and weir velocities with appropriate outlet protection				
	·	the of sediment from the site shall be prevented by the installation of erosion and sediment control		wate	after discharge points. oil series for the project site and their delineation.	To doorning day also larges male at order in the last	y, somodo di dii osom		
	measures and practices prior to land o		51-0010 54 Series		ne limits of disturbance for each phase of construction.				
		ndditional erosion and sediment control measures shall be implemented to control or treat the sediment	nt 51-0009	exc	rovide a minimum of 67 cubic yards of sediment storage per acre o xcavated inlet sediment traps for each common drainage location.	Sediment storage volume must be in place prior to	and during all land		
	51-0002 Yes 21 Clearly note the statement "Any disturt seeding,"	bed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary		conf	sturbance activities until final stabilization of the site has been achie ontrols when a sediment basin is not attainable must be included in ot provided. A written justification as to why 67 cubic yards of storag	the Plan for each common drainage location in which	n a sediment basin is		
	51-0011 Yes 22 Any construction activity which dischar	ges storm water into a Biota Impaired Stream Segment, or within 1 linear mile upstream of and within iota Impaired Stream Segment must comply with Part III.C. of the permit. Include the completed App		be i	e included for structural BMPs and all calculations used by the desi quivalent controls. When discharging from sediment basins and imp	gn professional to obtain the required sediment store	age when using		
	•	total impaired stream segment must comply with Part III.C. of the permit. Include the completed App chosen BMPs that will be used for those areas of the site which discharge to the Impaired Stream	ndix	wate	ater from the surface, unless infeasible. If outlet structures that withd is decision must be included in the Plan.		• I		
	51-0011 Yes 23 If a TMDL Implementation Plan for sed	iment has been finalized for the Biota Impaired Stream Segment (identified in Item 22 above) at least	54 Series		ocation of Best Management Practices that are consistent with, and eorgia. Use uniform coding symbols from the Manual Chapter 6, w		ediment Control in		
	Implementation Plan. *	S&PC Plan must address any site-specific conditions or requirements included in the TMDL	56 Series	Yes 51 Prov	rovide detailed drawings for all structural practices. Specifications and Sediment Control in Georgia.	•	he Manual for Erosion		
	at the construction site is prohibited. *	, concrete mixer chutes, hoppers and the rear of the vehicles. Include statement that washout of the .	51-0002/51-0003	Yes 52 Prov	rovide vegetative plan, noting all temporary and permanent vegetat nd mulching rates. Vegetative plan shall be site specific for approp				
	51-0004 Yes 25 Provide BMPs for the remediation of a 51-0004 Yes 26 Description of the measures that will b	all petroleum spills and leaks. e installed during the construction process to control pollutants in storm water that will occur after			no mulching rates. Vegetative plan shall be site specific for appropeographic region of Georgia.	made who or year mat securing will take prace and tof	ειο αμβιομιασ	GEORGISTER Y	
	construction operations have been co				using this checklist for a project that is less than 1 acre and not set the checklist items would be N/A.			* (No. 39533 PROFESSIONAL)	~
		used to reduce the pollutants in storm water discharges. *				Effective January	1, 2025	TREW I WILL	
		intended sequence of major activities which disturb soils for the major portions of the site (i.e., initials, clearing and grubbing activities, excavation activities, utility activities, grading, infrastructure, tempor						7/3/2025	
	and final stabilization).	·							
	Ţ	1	Т		1 /	REVISION DATES	=		
			_			ALVISION DATES		ENERAL NOTES	D.D.
		Kimley»	Horn		-		IULEWOOD RD	AT FELLOWSHIP	KU
		Engineering, Planning, And Enviro 3930 East Jones Bridge Ro	nmental Consultants			CHE	CKED:	DATE: DRAW	AWING No.
		Peachtree Comers, Georg		No	IOT TO SCALE	BAC	KCHECKED: RECTED:	DATE:	-0001
GPLN-CE 11/05/2020						VER	IFIED:	DATE: JI-	0001

gplotborder-ORD-PO.tbl

DESCRIPTION OF EXISTING SITE AND PROPOSED PROJECT

8 The existing site consists of a signalized fourway intersection between Idlewood Rd and Fellowship Rd.

The project proposes to convert the existing intersection of Idlewood Rd and Fellowship Rd to a hybrid multi-lane roundabout. The project will maintain existing drainage patterns. The existing footprint of the intersection will be widened to accommodate the roundabout geometry.

For additional information, see the project layout sheets included in the Plan Set.

ESPCP ALTERATIONS, AMENDMENTS, AND REVISIONS

This Erosion, Sedimentation, and Pollution Control Plan (ESPCP) is provided by the Department. It addresses the staged construction of the project on the basis of common construction methods and techniques. If the Contractor elects to alter the staged construction from that shown in the plans or utilize construction techniques that render this plan ineffective, the Contractor shall revise the plans in accordance to Special Provision 161-Control of Soil Erosion and Sedimentation of the contract.

The Contractor, the Certified Design Professional, and the WECS shall carefully evaluate this plan prior to commencing land-) disturbing activities. Amendments/revisions to

disturbing activities. Amendments/revisions to the ESPCP which have a significant effect on BMPs with a hydraulic component requires a formal revision of the ESPCP and the signature of a GSWCC Level-II Certified Design Professional. Additional BMPs may be added per Special Provision 161-Control of Soil Erosion and Sedimentation.

MAINTAINING EROSION CONTROL MEASURES

- (19) The escape of sediment from the project site shall be prevented by the installation of erosion and sediment control measures and practices prior to land-disturbing activities.
- (20) Erosion and sedimentation control measures will be maintained at all times. If full implementation of the approved plan does not provide for effective control, additional erosion and sedimentation control measures shall be implemented to control or treat the sediment source.

WASTE DISPOSAL

13933005_51.dgr

Where attainable, locate waste collection areas, dumpsters, trash cans and portable toilets at least 50 feet away from streets, gutters, watercourses and storm drains. Secondary containment shall be provided around liquid waste collection areas to minimize the likelihood of contaminated discharges. The Contractor shall comply with applicable state and local waste storage and disposal regulations and obtain all necessary permits.

18 Solid materials, including building materials, shall not be discharged to Waters of the State, unless authorized by a Section 404 Permit.

READY MIX CHUTE & TOOLS WASHDOWN

(24) The washing of ready-mix concrete drums and dump truck bodies used in the delivery of Portland cement concrete is prohibited on this site.

In accordance with Standard Specification 107: Legal Regulations and Responsibility to the Public, only the discharge chute utilized in the delivery of Portland cement concrete may be rinsed free of fresh concrete remains. The Contractor shall excavate a pit outside of State water buffers, at leas't 25 feet from any storm drain and outside of the travelled way, including shoulders, for a wash-down pit. The pit shall be large enough to store all washdown water without overtopping. Immediately after the wash-down operations are completed, the pit shall be filled in, and the ground above it shall be graded to match the elevation of the surrounding areas. Alternate wash-down plans must be approved by the Project Engineer.

Wash-down plans describe procedures that prevent wash-down water from entering streams and rivers. Never dispose of wash-down water down a storm drain. Establish a wash-down pit that includes the following: (1) a location away from any storm drain, stream, or river, (2) access to the vehicle being used for wash down, (3) sufficient volume for wash-down water, and (4) permission to use the area for wash down.

On sites where permission or access to excavate a wash-down pit is unavailable, the Contractor may have to wash-down into a sealable 55-gallon drum or other suitable container and then transport the container to a proper disposal site. For additional information, refer to the Georgia Small Business Environmental Assistance Program's "A Guide for Ready Mix Chute/Hopper Wash-down".

SITE STABLIZATION AND VEGETATION PLANTING SCHEDULE

- (21) Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding.
 - The EPD General NPDES GAR100002 permit indicates that the disturbed area where construction activities have temporarily or permanently ceased shall be stabilized within 14 days of such cessation or as soon as practicable if precluded by adverse weather conditions. However, in special cases, the Project Engineer may require the contractor to perform stabilization more often than 14 days.

Disturbed areas shall be stabilized with suitable material listed in the current edition of the Department's Standard Specifications (or Special Provisions) Sections 161, 163, 700, or 711 on the basis of when construction activities are expected to resume.

All temporary and permanent vegetative practices including plant species, planting dates, seeding, fertilizing, liming, and mulching rates for this project can be found in Section 700 of the current edition of the Department's Standard Specifications (or Special Provisions) and other applicable contract documents or landscaping plans.



GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001

Kimley »Horn

nglneering, Planning, And Environmental Consultar 3930 East Jones Bridge Road, Sulte 350

NOT TO SCALE

REVISION DATES

ESPCP GENERAL NOTES

IDLEWOOD RD AT FELLOWSHIP RD

CHECKED: DATE: DRAWING No.

<u>SITE STABLIZATION AND VEGETATION PLANTING</u> <u>SCHEDULE (CONT'D)</u>

(52)

Ds1 - MULCHING				
MATERIAL	DEPTH			
DRY STRAW OR HAY	2° TO 4°			
WOOD WASTE (SAWDUST. BARK. CHIPS)	2. 10 3.			
CUTBACK ASPHALT (SLOW CURING)	1200 GAL. / ACRE (1/4 GAL. / SO.YD.)			
BLACK POLYETHYLENE FILM	COMPLETELY COVER AREA; HOLD IN PLACE WITH SOIL ON OUTER EDGE			

Ds2 - TEMPORARY SEEDING						
	PLANTS, PLANTING RATES, AND PLANTING DATES					
FOR I	LMPURARY	COVER OF	? COMPANIO	IN CROPS		
SPECIES	RATES PER	RATES PER	PLANT	ING DATES BY F	EGION	
SPECIES	1.000 SQ. FT.	ACRE	N-L	P	С	
BARLEY	3. 3 LBS.	3 BU.	9/1-10/31	9/15-11/15	10/1-12/31	
OATS	3. 3 LBS.	3 BU.	9/1-10/31	9/15-11/15	10/1-12/31	
TRITCALE	3. 3 LBS.	3 BU.	9/1-10/31	9/15-11/15	10/1-12/31	
RYEGRASS. ANNUAL	0.9 LBS.	40 LBS.	8/15-11/15	9/15-12/15	9/15-12/31	
RYE LESPEDEZA.	0.6 LBS.	0.5 BU.	8/15-10/31	9/15-11/30	10/1-12/31	
ANNUAL	0.9 LBS.	40 LBS.	3/1-3/31	3/1-3/31	2/1-2/28	
WEEPING LOVEGRASS	0. / LBS.	4 LBS.	4/1-5/31	4/1-5/31	3/1-5/31	
SUDANGRASS	I. 4 LBS.	60 LBS.	4/1-8/31	4/1-8/31	3/1-7/31	
WILLET, BROWNTOP	0.9 LBS.	40 LBS.	4/15-6/15	10/1-12/15	10/15-12/31	
MILLET, PEARL	I.I LBS.	50 LBS.	5/15-7/15	10/1 12/13	10/13 12/31	
WHEAT	4. I LBS.	3 BU.	9/15-11/30	10/1-12/15	10/15-12/31	

- I. TEMPORARY COVER CROPS ARE VERY COMPETITIVE AND WILL CROWN OUT PERENNIALS IF PLANTED TOO HEAVILY.
- 2. REDUCE SEEDING RATES BY 50% WHEN DRILLED.
- 3. UNUSUAL SITE CONDITIONS MAY REQUIRE HEAVIER SEEDING RATES.
- 4. SEEDING RATES WAY NEED TO BE ALTERED TO FIT TEMPERATURE VARIATIONS AND LOCAL CONDITIONS.
- M-L REPRESENTS THE MOUNTAIN, BLUE RIDGE, AND RIDGES & VALLEYS MLRAS.
- P REPRESENTS THE SOUTHERN PIEDMONT REGION MLRA.
- C REPRESENTS THE SOUTHERN COASTAL PLAIN, SAND HILLS, BLACK LANDS, AND ATLANTIC COAST FLATWOODS MLRAS.

FERTILIZER REQUIREMENTS FOR TEMPORARY VEGETATION						
TYPES OF SPECIES	PLANTING	FERTILIZER	RATE	N TOP DRESSING		
	YEAR	(N-P-K)	(LBS./ACRE)	RATE (LBS./ACRE)		
COOL SEASON GRASSES	FIRST	6-12-12	1500	50-100		
	SECOND	6-12-12	1000	-		
	MAINTENANCE	10-10-10	400	30		
COOL SEASON GRASSES & LEGUMES	FIRST	6-12-12	1500	0-50		
	SECOND	0-10-10	1000	-		
	MAINTENANCE	0-10-10	400	-		
TEMPORARY COVER CROPS	FIRST	10-10-10	500	30		
SEEDED ALONE WARM SEASON GRASSES	FIRST SECOND MAINTENANCE	6-12-12 6-12-12 10-10-10	1500 800 400	50-100 50-100 30		

	Ds3 - PERMANENT GRASSING					
PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER						
TYPES OF SPECIES		RATES PER	PLANTII M-L	IG DATES BY	REGION C	REMARKS
BAHIA, PENSACOLA ALONE OR WITH TEMPORARY COVER WITH PERENNIALS	60 LBS. 30 LBS.	1. 4 LBS. 0. 7 LBS.	-	4/1-5/31	3/1-5/31	LOW GROWING AND SOD FORMING. ALLOW TO ESTABLISH. WILL SPREAD INTO BERMUDA LAWNS.
BAHIA, WILMINGTON ALONE OR WITH TEMPORARY COVER WITH PERENNIALS	60 LBS. 30 LBS.	1.4 LBS. 0.7 LBS.	3/15-5/31	3/1-5/31	-	LOW GROWING AND SOD FORMING. ALLOW TO ESTABLISH. WILL SPREAD INTO BERMUDA LAWNS.
BERMUDA, COMMON (HULLED SEED) ALONE OR WITH TEMPORARY COVER WITH PERENNIALS	10 LBS. 6 LBS.	0. 2 LBS. 0. 1 LBS.	1	4/1-5/31	3/15-5/31	QUICK COVER, LOW GROWING AND SOD FORMING. NEEDS FULL SUN.
BERMUDA, COMMON (UNHULLED SEED) ALONE OR WITH TEMPORARY COVER WITH PERENNIALS	10 LBS. 6 LBS.	0. 2 LBS. 0. I LBS.	-	10/1-2/28	11/1-1/31	PLANT WITH WINTER ANNUALS PLANT WITH TALL FESCUE
BERMUDA, SPRIGS TEMPORARY COVER	40 CF SOD PLUG	0.9 CF S 3' X 3'	4/15-6/15	4/15-6/15	4/1-5/31	I CF · 650 SPRIGS I BU. · I.25 CF OR 800 SPRIGS.
CENTIPEDE	BLOCK S	SOD ONLY	-	11/1-5/31	11/1-5/31	DROUGHT TOLERANT: FULL SUN OR PARTIAL SHADE; EFFECTIVE ADJACENT TO CONCRETE AND IN CONCENTRATED FLOW AREAS; IRRIGATION NEEDED UNTIL FULLY ESTABLISHED; DO NOT PLANT NEAR PASTURES.
CROWN VETCH WITH WINTER ANNUALS OR COOL WINTER GRASSES	15 LBS.	0. 3 LBS.	9/1-10/15	9/1-10/10	-	MIX WITH 30 LBS. TALL FESCUE OF 15 LBS. RYE: INNOCULATE SEED: ONLY NORTH OF ATLANTA. DENSE GROWTH: DROUGHT TOLERANT AND FIRE RESISTENT
FESCUE, TALL ALONE WITH OTHER PERENNIALS	50 LBS. 30 LBS.	1. 1 LBS. 0.7 LBS.	3/1-4/1 OR 8/15-10/15	9/1-10/15 OR 2/15-4/15	-	NOT FOR DROUGHTY SOILS. MIX WITH PERENNIAL LESPEDEZAS OR CROWNVETCH. APPLY TOPDRESSING IN SPRING FOLLOWING FALL PLANTINGS. NOT FOR HEAVY USE AREAS OR ATHLETIC FIELDS. 227,000 SEED PER POUND.
LESPEDEZA, SERICEA SCARIFIED	60 LBS.	1.4 LBS.	4/1-5/31	3/15-5/31	3/1-5/15	WIDELY ADAPTED AND LOW MAINTENANCE. TAKES 2-3 YEARS TO ESTABLISH. EXCELLENT ON ROADBANKS. INOCULATE SEED WITH EL INOCULANT. MIX WITH WEEPING LOVEGRASS, COMMON BERMUDA, HAHIA, OR TALL FESCUE.
UNSCARIFIED	75 LBS.	1.7 LBS.	9/1-2/28	9/1-2/28	9/1-2/28	MIX WITH TALL FESCUE OR WINTER ANNUALS
SEED-BEARING HAY	3 TONS	138 LBS.	10/1-1/31	10/1-1/31	9/15-1/15	CUT WHEN SEED IS MATURE. BUT BEFORE IT SHATTERS. ADD TALL FESCUE OR WINTER ANNUALS.
LESPEDEZA, AMBRO VIRGETA OR APPALOW SCARIFIED UNSCARIFIED	60 LBS. 75 LBS.	I. 4 LBS. I. 7 LBS.	4/1-5/31 9/1-2/28	3/15-5/31 9/1-2/28	3/15-5/15 9/1-2/28	SPREADING GROWTH WITH HEIGHT OF 18"-24". GOOD IN URBAN AREAS. MIX WITH WEEPING LOVEGRASS. COMMON BERWIDA, BAHIA, TALL FESCUE, OR WINTER ANNUALS. DO NOT MIX WITH SERICEA LESPEDEZA. SLOW TO DEVELOP SOLID STANDS. INOCULATE SEED WITH EL INOCULANT.
LESPEDEZA, SHRUB (LESPEDEZA BICOLOR OR LESPEDEZA THUMBERGIL) PLANTS	3' X 3'	SPACING	10/1-3/31	11/1-3/15	11/15-2/28	PLANT IN SMALL CLUMPS FOR WILDLIFE FOOD AND COVER.
LOVEGRASS, WEEPING ALONE WITH OTHER PERENNIALS	4 LBS. 2 LBS.	0. I LBS 0. 05 LBS	4/1-5/31	3/15-5/31	3/1-5/31	QUICK COVER. DROUGHT TOLERANT. GROWS WELL WITH SERICEA LESPEDEZA ON ROADBANKS.
MAIDENCANE SPRIGS	2' X 3'	SPACING	2/1-3/31	2/1-3/31	2/1-3/31	FOR VERY WET SITES SUCH AS RIVERBANKS AND SHORELINES. DIG SPRIGS LOCALLY. MAY CLOG CHANNELS.
PANICGRASS, ATLANTIC COASTAL	20 LBS.	0.5 LBS	-	3/1-4/30	3/1-4/30	GROWS WELL ON COASTAL SAND DUNES, BORROW AREAS, AND GRAVEL PITS. PROVIDES WINTER COVER FOR WILDLIFE. MIX WITH SERICEA LESPEDEZA EXCEPT ON SAND DUNES.
REED CANARY GRASS ALONE WITH OTHER PERENNIALS	50 LBS. 30 LBS.	1. 1 LBS. 0. 7 LBS.	6/15-10/15	9/1-10/15	-	GROWS SIMILAR TO TALL FESCUE
SUNFLOWER, 'AZTEC' MAXIMILLIAN	IO LBS.	0. 27 LBS.	4/15-5/31	4/15-5/31	4/1-5/31	MIX WITH WEEPING LOVEGRASS, LEGUMES, OR OTHER LOW GROWING GRASSES.

Ds3 - PERMANENT SEEDING						
FERTILIZER REQUIREMENTS FOR PERMANENT VEGETATION						
TYPES OF SPECIES	PLANTING	FERTILIZER	RATE	N TOP DRESSING		
	YEAR	(N-P-K)	(LBS. /ACRE)	RATE (LBS./ACRE)		
COOL SEASON GRASSES	FIRST	6-12-12	1500	50-100		
	SECOND	6-12-12	1000	-		
	WAINTENANCE	10-10-10	400	30		
COOL SEASON GRASSES & LEGUMES	FIRST	6-12-12	1500	0-50		
	SECOND	0-10-10	1000	-		
	MAINTENANCE	0-10-10	400	-		
GROUND COVERS	FIRST	10-10-10	1300	-		
	SECOND	10-10-10	1300	-		
	MAINTENANCE	10-10-10	1300	-		
PINE SEEDLINGS	FIRST	20-10-5	ONE 21-GRAM PELLET PER SEEDLING PLACED IN THE CLOSING HOLE	-		
SHRUB LESPEDEZA	FIRST WAINTENANCE	0-10-10 0-10-10	700 700	-		
TEMPORARY GROUND COVER CROPS SEEDED ALONE	FIRST	10-10-10	500	30		
WARN SEASON GRASSES	FIRST	6-12-12	1500	50-100		
	SECOND	6-12-12	800	50-100		
	MAINTENANCE	10-10-10	400	30		
WARM SEASON GRASSES & LEGUMES	FIRST	6-12-12	1500	50		
	SECOND	0-10-10	1000	-		
	MAINTENANCE	0-10-10	400	-		



GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001 APPLY AGRICULTURAL LIME AS PRESCRIBED BY SOIL TESTS OR AT A RATE OF 1-2 TONS PER ACRE

REVISION DATES

Kiml	ey»	Horn
Englished Bloo		

Engineering, Planning, And Environmental Consultants 3930 East Jones Bridge Road, Sulte 350 Peachtree Corners, Georgia 30092

ESPCP GENERAL NOTES IDLEWOOD RD AT FELLOWSHIP RD

			CHECKED:	DATE:	DRAWING No
		BACKCHECKED:	DATE:		
			CORRECTED:	DATE:	J 51.000
	VERIFIED:	VERIFIED:	DATE:	<u> </u>	

NON-STORMWATER DISCHARGES

Non-stormwater discharges defined in Part III.A.2 of the NPDES Permit will be identified after construction has commenced. These discharges shall be subject to the same requirements as storm water discharges required by the Georgia Erosion and Sedimentation Control Act, the NPDES Permit, the Clean Water Act, the Manual for Erosion and Sediment Control in Georgia, Department Standards, and other contract documents. The NPDES does not authorize the discharge of soaps or solvents used in vehicle and equipment washing or the discharge of wastewater containing stucco, paint, oils, curing compounds, and other construction materials.

PETROLEUM STORAGE, SPILLS AND LEAKS

(25) These plans expressly delegate the responsibility of proper on-site hazardous material management to the Contractor. The Contractor shall at a minimum provide an action plan and keep the necessary materials on site for the capture, clean up, and disposal of any petroleum product, or other hazardous material, leaks or spills associated with the servicing, refueling or operation of any equipment utilized at the site. A copy of the action plan shall be submitted to the Project Engineer and maintained on the project site. All personnel operating or servicing equipment shall be familiar with the action plan. The Contractor shall not park, refuel, or maintain equipment within stream buffers.

If the Contractor elects to store petroleum products on site, the Contractor shall prepare an ESPCP addendum that addresses the additional BMPs needed for onsite storage and spill prevention for petroleum products. This plan shall be prepared by a Certified Design Professional as required by GAR100002 for inclusion with these plans. The Contractor's attention is specifically directed to Standard Specification 107-Legal Regulations and Responsibility to the public for additional requirements.

The phone number for the Georgia Nuclear Regulatory Commission is 1-800-424-8802.

POSTCONSTRUCTION BMPs FOR STORMWATER MANAGEMENT

(26) All permanent postconstruction BMPs are shown in the construction plans and in the ESPCP plan. The postconstruction BMPs for this project consist of vegetation where necessary. The postconstruction BMPs will provide permanent stabilization of the site and prevent abnormal transportation of sediment and pollutants into receiving waters.

DISTURBED AREA STABILIZATION (WITH MULCHING ONLY) Ds1

- $(28)\,1$. Mulch or temporary grassing shall be applied to all exposed areas within 14 days of disturbance.
 - 2. Mulch shall have a continous 90% cover or greater of the soil surface.
 - 3. Select one of the following mulching materials and apply at the depth indicated:
 - a. Dry straw or hay shall be applied at a depth of 2 to 4 inches providing complete soil coverage. Mulch shall be anchored immediately after application by hand or by mechancial equipment. When spread with blower-type equipment, mulch shall be anchored with emulsified asphalt sprayed onto the mulch as it is ejected from the machine.
 - b. Wood waste (chips, sawdust, or bark) retained from the clearing stages, or acquired otherwise, shall be applied at a depth of 2 to 3 inches. Netting of the appropriate size shall be used to anchor thee wood waste.
 - c. Cutback asphalt (slow curing) shall be applied at 1200 gal. per acre.
 - d. Polyethylene film shall be secured over banks or stockpiled soil material for temporary protection. The film shall be anchor trenched at the top as well as incrementally as necessary.
 - 4. Maintenance shall be required to maintain appropriate depth and 90% cover.

DISTURBED AREA STABILIZATION (WITH TEMPORARY SEEDING) DS2

- $^{(28)}1$. Mulch or temporary grassing shall be applied to all exposed areas within 14 days of disturbance.
- 2. Temporary grassing, instead of mulch, can be applied to rough graded areas that will be exposed for less than 6 months. If an area is expected to be undisturbed for more than 6 months, permanent perennial vegetation shall be used.
- 3. 10-10-10 fertilizer shall be applied at a rate of 500-700 lbs per acre before land preparation and incorporated with a disk, ripper, or chisel.

DISTURBED AREA STABILIZATION (WITH PERMANENT VEGETATION) [DS3]

- (28) 1. Permanent vegetation shall be applied immediately to rough graded areas that will be undisturbed longer than 6 months.
 - 2. Prepare the ground by plowing under any temporary grass and mulch areas and plowing the ground to a depth of 4 to 6 inches. Plowing shall be done on the contour, where feasible.
 - 3. 6-12-12 or equivalent fertilizer shall be applied at a rate of 1500 lbs per acre.
 - 4. Agricultural lime shall be applied at a rate of 1 to 2 tons per acre unless soil tests indicate otherwise.
 - 5. Mulch shall be applied to permanent grassing areas such that 75% cover is achieved at the following rates:
 - A. Dry straw 2 tons per acre
 - B. Dry Hay 2 1/2 tons per acre
 - C. Wood Cellulose Mulch or Wood Pulp Fiber -500 lbs per acre
 - D. Sericea Lespedeza Hay containing mature seed - 3 tons per acre

DISTURBED AREA STABILIZATION (WITH SODDING) DS4

- (28) 1. Permanent sodding shall be applied immediately to final grading areas that will be undisturbed throughout the remainder of construction.
 - 2. Prepare soil surface to grade and clear surface of any trash, woody debris, stone and clods larger than 1".
 - 3. 10-10-10 fertilizer shall be applied at a rate of 1000 lbs per acre and agricultural lime should be applied at a rate of 1 to 2 tons per acre for soil surface preparation unless soil tests indicate otherwise.
 - 4. Sod must be staked on slopes steeper than 3:1 and in areas of concentrated flow.
 - 5. Irrigate sod and soil to a depth of 4" immediately after installation.

CONSTRUCTION SCHEDULE AND SEQUENCE OF MAJOR *ACTIVITIES*

(28) The Contractor is responsible for developing the construction schedule for the project. The 29) construction schedule for this project shall be submitted after the project is awarded along with the NOI. A copy of the construction schedule shall be maintained at the project site.

ACTIVITY	MONTH I	MONTH 2	MONTH 3	MONTH 4	MONTH 5	MONTH 6
TEMP. EROSION & SEDIMENT CONTROL						
INITIAL PERIMETER CONTROL						
CLEARING, GRUBBING & GRADING						
TEMPORARY GRASSING						
CONSTRUCTION OF DRAINAGE						
CONSTRUCTION OF CURB & GUTTER, SIDEWALK						
CONSTRUCTION OF BASE & PAVING						
FINAL GRASSING/PERM. EROSION & SED. CONTROL DEVICES						
REMOVAL OF TEMP. SED. CONTROL DEVICES						

The project budget includes sufficient funds for the payment of construction exits. The Contractor is responsible for establishing at least one (1) construction exit per the specifications of the construction exit detail included in this ESPCP to minimize or eliminate the vehicle tracking of dirt, soils, and sediments off site. To facilitate project logistics, the Contractor is also responsible for selecting the location(s) of the construction exit(s).



GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001

Kimley Morn

3930 East Jones Bridge Road, Sulte 350

NOT TO SCALE

REVISION DATES		ESPCP GENERAL NOTES					
			1	23, 0,	CLITE		., 20
] I	DLEWOOD	RD AT	FELLO	NSHIP RD
			CHECKED:		DATE:		DRAWING No.
			BACKCHECKED:		DATE:		
			CORRECTED:		DATE:		51-0004
			VERIFIED:		DATE:		71-0004

CONSTRUCTION SCHEDULE AND SEQUENCE OF MAJOR ACTIVITIES (CONT'D)

- (36) Initial Phase BMP Installation:
 - 1. Perimeter control silt fence shall be installed as shown in the Initial Phase BMP Location Detail Sheets beginning with construction exits. Certified personnel shall conduct inspections in accordance with the NPDES Permit GAR 100002 throughout the entire project duration.
 - 2. Inlet sediment traps shall be installed on existing drainage structures as shown on the Initial Phase BMP Location Details.
 - 3. A 7-day inspection must be performed.
 - 4. Maintain and repair or replace all temporary BMP's as necessary

Stage 1 - Intermediate Phase

This work includes clearing and grubbing, milling and leveling of existing roadways, widening of existing roadways, construction of curb and gutter and sidewalks, construction of residential driveways, and construction of drainage structures and pipes. Temporary BMP's should remain in place until all earthmoving activities have ceased and stabilization has been achieved, unless their removal is necessary for the construction of the roadway improvements.

Intermediate BMP Installation:

- 1. As proposed drainage features are constructed, the associated BMP's shall be installed as soon as practical.
- 2. Install temporary grassing and mulch per the requirements of the NPDES General Permit NO. GAR100002 to disturbed areas.
- 3. Maintain and repair or replace all temporary BMP's, as necessary, untill all earthmoving activities have ceased and final stabilization has been achieved for the entire stage, unless removal is necessary for the construction of the roadway

Stagėmprovements.

This work includes clearing and grubbing, milling and leveling of existing roadways, full depth construction, and construction of new sidewalk. Temporary BMP's should remain in place until all earthmoving activities have ceased and stabilization has been achieved, unless their removal is necessary for the construction of the roadway improvements.

GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001 Intermediate BMP Installation:

- 1. As proposed drainage features are constructed, the associated BMP's shall be installed as soon as practical.
- 2. Install temporary grassing and mulch per the requirements of the NPDES General Permit NO. GAR100002 to disturbed areas.
- 3. Maintain and repair or replace all temporary BMP's, as necessary, untill all earthmoving activities have ceased and final stabilization has been achieved for the entire stage, unless removal is necessary for the construction of the roadway improvements.

Stage 3

This work includes constructing concrete medians. Temporary BMP's should remain in place until all earthmoving activities have ceased and stabilization has been achieved, unless their removal is necessary for the construction of the roadway improvements.

Final Phase BMP Installation:

- 1. Install permanent vegetation on all disturbed areas where finished grade has been established as shown in the Final Phase BMP location detail sheets.
- 2. Maintain and repair or replace all temporary BMP's, as necessary, until all earthmoving activities have ceased and final stabilization has been achieved for the entire project. At this time, all temporary BMP's can be removed.

OTHER CONTROLS

27 If the Contractor elects to store building material, building products, construction waste, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste, and other materials on the site, the Contractor shall provide an appropriate covering to minimize the exposure of those materials or products to precipitation and stormwater to minimize the discharge of pollutants.

Minimization of exposure is not required in cases where exposure to precipitation and to stormwater will not result in a discharge of pollutants, or where exposure of the specific material or product poses little risk to stormwater contamination or is intended for outdoor use.

The Contractor shall follow this ESPCP and ensure and demonstrate compliance with all applicable State and/or local regulations for waste disposal, sanitary sewer and septic systems, and petroleum storage.

The Contractor shall control dust from the site in accordance with Section 161 of the current edition of the Department's Standard Specifications.

INSPECTIONS AND REPORTING

(30) As the primary permittee, the Department must retain the design professional who prepared the ESPCP, or an alternative design professional approved by EPD in writing, to inspect and certify the installation of the initial sediment storage requirements and perimeter control BMPs within 7 days of installation over the entire infrastructure project. Alternatively, for linear infrastructure projects, the permittee must retain either of these personnel to inspect the initial sediment storage requirements and perimeter control BMPs for the initial segment, as defined by Part IV.A.5. of the current GAR100002 Permit, within 7 days of installation and all sediment basins within the entire linear infrastructure project within 7 days of installation. The inspecting design professional shall report the results to the primary permittee within 7 days, and the permittee must correct all deficiencies within 2 business days of receipt of the inspection report, unless on-site weather conditions are such that more time is required. Additionally, the Department's Construction Project Engineer will be responsible for all subsequent 7-day inspections for all new BMP installations.

All other inspections shall be documented on the appropriate Department inspection forms. See Standard Specification (or Special Provision) 167 and other contract documents for inspection and reporting requirements. These inspections shall continue until the Notice of Termination (NOT) is submitted.



Kim	ley»Horn
Castanastas Die	andra And Francisconnectal Consultanta

Englneering, Planning, And Environmental Consulta 3930 East Jones Bridge Road, Sulte 350 Peachtree Corners, Georgia 30092

/\L V 1 .	JION L	77163	
			l
			l
			CHE
			BAC
			COG

NOT TO SCALE

I REVISION DATES I

ESPCP GENERAL NOTES
IDLEWOOD RD AT FELLOWSHIP RD

CHECKED: DATE: DRAWING NO BACKCHECKED: DATE: CORRECTED: DATE: 51 - 000!

INSPECTIONS AND REPORTING (CONT'D)

Whenever the Department finds that a BMP has failed or is deficient beyond routine maintenance and has resulted in sediment deposition into waters of the State, the Contractor shall take reasonable steps to address the condition, including cleaning up any contaminated surfaces so the material will not discharge in subsequent storm events. When the repair does not require a new or replacement BMP or significant repair, the BMP failure or deficiency must be corrected by the close of the next business day from the time of discovery. A repair requiring a new or replacement BMP or significant repair must be operational by no later than 7 days from the time of discovery. If the repair time within 7 days is infeasible, the Contractor and the Department shall schedule the BMP repair to be operational as soon as practical after the 7day time frame.

Failure to perform inspections as required by the contract documents and the NPDES permit shall result in the cessation of all construction activities with the exception of Traffic Control and Erosion Control. Continued failure to perform inspections shall result in non-refundable deductions as specified in the contract documents.

Permittee requirements.

- (1). Each day when any type of construction activity has taken place at a Primar Permittee's site, certified personnel provided by the Primary Permittee shall inspect: (a) all areas at the Primary Permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the Primary Permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termination is submitted.
- (2). Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working Saturday, nonworking Sunday and non-working Federal holiday. The data collected for the purpose of compliance with this permit shall be representative of the monitored activity. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.

- (3). Certified personnel (provided by the Primary Permittee) shall inspect the following at least once every fourteen (14) calendar days: (a) disturbed areas of the Primary Permittee's construction site; (b) areas used by the Primary Permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the Primary Permittee's site shall be observed to ensure that they are operating correctly. Certified personnel shall also conduct inspections within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any non-working Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first). Post-rain inspections will reset the 14-day inspection frequency requirement. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.
- (4). Certified personnel (provided by the Primary Permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is submitted to EPD) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).

- (5). Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.
- (6). A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5). of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction site that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify any incidents, the inspection report shall contain a statement that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

APPROPRIATE BMP AND SAMPLING CERTIFICATION STATEMENT

The permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated in Part IV page 20 of the permit. The signature of the preparer affixed on the Plan cover sheet serves as the certification.

(31) WATER QUALITY INSPECTING AND SAMPLING PROCEDURES

See Special Provision 167 and other contract documents for the inspecting and sampling procedures. Sampling locations are provided in the Sampling Location table herein.

GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001

Kimley » Horn

Ineering, Planning, And Environmental Consultar 3930 East Jones Bridge Road, Suite 350

REVISION DATES

ESPCP GENERAL NOTES
IDLEWOOD RD AT FELLOWSHIP RD

CHECKED: DATE: DRAWING NO
BACKCHECKED: DATE:
CORRECTED: DATE: 5.1 0.00

NOT TO SCALE

7/3/2025

(31) REPORT ING

All written correspondence required by this permit shall be submitted by return receipt certified mail (or similar service) to the appropriate EPD District Office or delivery receipt email to the appropriate EPD District Office resource mailbox according to the schedule in Appendix A of this permit. The permittee shall retain a copy of the proof of submittal at the construction site or the proof of submittal shall be readily available at a designated location from commencement of construction until such time as a NOT is submitted in accordance with Part VI.

RETENTION OF RECORDS

- (32) 1. The Primary Permittee shall retain the following records at the construction site or the records shall be readily available at a designated alternate location from commencement of construction until such time as a NOT is submitted in accordance with Part VI:
 - a. A copy of all Notices of Intent submitted to EPD;
 - b. A copy of the Erosion, Sedimentation and Pollution Control Plan required by this permit;
 - c. The design professional's report of the results of the inspection conducted in accordance with Part IV.A.5. of this permit;
 - d. A copy of all sampling information, results, and reports required by this permit:
 - e. A copy of all inspection reports generated in accordance with Part IV.D.4.a. of this permit;
 - f. A copy of all violation summaries and violation summary reports generated in accordance with Part III.D.2. of this permit; and
 - g. Daily rainfall information collected in accordance with Part IV.D.4.a.(2). of this permit.

2. Copies of all Notices of Intent, Notices of Termination, inspection reports, sampling reports (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation), or other reports requested by the EPD, Erosion, Sedimentation and Pollution Control Plans, records of all data used to complete the Notice of Intent to be covered by this permit and all other records required by this permit shall be retained by the permittee who either produced or used it for a period of at least three vears from the date that the NOT is submitted in accordance with Part VI of this permit. These records must be maintained at the permittee's primary place of business or at a designated alternative location once the construction activity has ceased at the permitted site. This period may be extended by request of the EPD at any time upon written notification to the permittee.

SILT FENCE INSTALLATION WITH J HOOKS AND SPURS

Silt fence should never be run continuously. The silt fence should turn back into the fill or slope to create small pockets that trap silt and force stormwater to flow through the silt fence. This technique is called using J hooks (or spurs). The J hooks shall be utilized on all silt fences that are located around the perimeter of the project and along the toe of embankments or slopes. The J hooks shall be spaced in accordance with GDOT Construction Detail D-24C. The maximum J-hook spacing is reached when the top of the J hook is at the same elevation as the bottom of the immediately upgradient J hook. J Hooks shall be paid for as silt fence items per linear foot. All costs and other incidental items are included in the cost of installing and maintaining the silt fence.

BMP INSTALLATION AND MAINTENANCE MEASURES

See the Department's Standard Specifications (or Special Provisions) 161, 163, 165, 700, 711, and other contract documents for installation and maintenance measures.

DEWATERING AND PUMPING ACTIVITIES

Any pumped discharge from an excavation or disturbed area shall be routed through an appropriately sized sediment basin, silt filter bag, or shall be treated equivalently with suitable BMP's. The contractor shall ensure the post BMP treated discharge is sheet flowing. Failure to create sheet flow will obligate the contractor to perform water quality sampling of pumped discharges. The contractor shall prepare sampling plans in accordance with the current GAR100002 NPDES permit by utilizing a Certified Design Professional. No separate payment will be made for water quality sampling of pump discharges.

USE OF ALTERNATIVE AND/OR ADDITIONAL BMPS

(39) No alternative or additional BMPs will be used on this project.

STATE WATER BUFFER IMPACTS

State water buffers, as defined by O.C.G.A. (16) 12-7-1, are not impacted by this project.

Non-exempt activities shall not be conducted within the 25- or 50-foot undisturbed stream buffers as measured from the point wrested vegetation or within 25-feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary variances and permits.

RIPRAP OUTLET PROTECTION

Outlet protection is not required for this project.



##) GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001

Engineering, Planning, And Environmental Consultants 3930 East Jones Bridge Road, Suite 350

F			

REVISION DATES

ESPCP GENERAL NOTES

IDLEWOOD RD AT FELLOWSHIP RD

CHECKED: DATE: DRAWING NO

SAMPLING LOCATIONS AND GENERAL NOTES

(10) Representative sampling may be utilized on this project as explained here. The individual outfall drainage basins along the project corridor have been carefully evaluated and compared on the basis of four characteristics: the type of construction activity, the disturbed acreage, the average slope about the outfall, and the soil erosion index 0-10, 10 being the most erodible soil. The construction activity types are new road on fill, new road in cut, road widening, and maintenance/safety. The disturbed area classes are less than or equal to 1 acre, greater than 1 acre to less than 2 acres, and equal to or greater than 2 acres. The average outfall slope is mild if it is equal to or less than 0.03, and steep if it is greater than 0.03. The soil erosion index is low if it is less than or equal to 5 and high if it is greater than 5. After evaluation of these characteristics as presented in the project's drainage area map, hydrology and hydraulic studies, construction plans, geotechnical soil survey, and erosion sedimentation and pollution control plans, the Department has determined that the representative sampling scheme shown below is valid for the duration of the project. The table shows the groups of similar outfall drainage basins.

The increase in turbidity at the specified locations in the table below will be representative of the alternate outfall drainage basins when similar outfall drainage basins exist. Approved primary and alternate representative sampled features are identified in the Sampling Location Table.

The primary sampled features specified should be used as the initial sampling locations. An alternate sampled feature may be used if additional sampling is required or to replace a primary sampled feature that is no longer located within the active phase of construction.

The permittee's ES&PC Plan provides for representative sampling as stated on Part IV.D.6.c.(3) page 37 of the permit as applicable. The signature of the preparer affixed on the Plan cover sheet serves as the certification.

34		SAMPLING LOCATION TABLE										Rep	resentativ	e Samplir	ng Schei	me
(35)				Sai	mpling Informa	tion							Outfall (Characteri	stics	
	Primary Sampled Feature	Location (Station and Offset)	Name of Receiving Water	Applicable Construction Stage for Sampling	Sampling Type (Outfall or Receiving water)	Drainage Area for Receiving Water (mi ²)	Upstream Disturbed Area (acres)	Warm or Cold Water Stream	Appendix B NTU Value (Outfall Sampling only)	Allowable NTU Increase (Receiving water sampling only)	Location Description	Construction Activity	Disturbed Area (acres)	Average Outfall Slope (Rise/Run)	Soil Erosion Index	Represented Outfall Drainage Basins
	Outfall A	STA. 107+12.40, 26.46′ LT	South Fork Peachtree Creek	All	Outfall	0.92	N/A	Warm	<i>7</i> 5	N/A	Existing Catch Basin	Road Widening	<1	Mild	Mild	Outfall B

Storm water is to be sampled for nephelometric turbidity units (NTU) at the outfall location. A discharge of storm water runoff from disturbed areas where best management practices have not been properly designed, installed, and maintained shall constitute a separate violation for each day on which such conditions results in the turbidity of the discharge exceeding 75, the value that was selected from Apendix B in Permit No.GAR 100002. The NTU is based upon the site area of 2.80 acres, the surface water drainage area of 0.92 square miles, and receiving water which supports warm water fisheries.

Sample Type. All sampling shall be collected by "grab samples" and the analysis of these samples must be conducted in accordance with methodology and test procedures established by 40 CFR Part 136 (unless other test procedures have been approved), the quidance document titled "NPDES Storm Water Sampling Guidance Document, EPA 833- B-92-001" and quidance documents that may be prepared by the EPD.

(2). Samples should be well mixed before transferring to a secondary container.

(1). Sample containers should be labeled prior to collecting the samples.

(3). Large mouth, well cleaned and rinsed glass or plastic jars should be used for collecting samples. The jars should be cleaned thoroughly to avoid 7/3/2025contamination.

(4). Manual, automatic or rising stage sampling may be utilized. Samples required by this permit should be analyzed immediately, but in no case later than 48 hours after collection. However, samples from automatic samplers must be collected no later than the next business day after their accumulation, unless flow through automated analysis is utilized. If automatic sampling is utilized and the automatic sampler is not activated during the qualifying event, the permittee must utilize manual sampling or rising stage sampling during the next qualifying event. Dilution of samples is not required. Samples may be analyzed directly with a properly calibrated turbidimeter. Samples are not required to be cooled.

(5). Sampling and analysis of the receiving water(s) or outfalls beyond the minimum frequency stated in this permit must be reported to EPD as specified in Part IV.E.

> GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001

	Kimley»Horn		REV I	SION I	DATES	1	ESPCP G IDLEWOOD RD	GENERAL NO AT FELLO	
	Englneering, Planning, And Environmental Consultants 3930 East Jones Bridge Road, Suite 350					CHECKED:		DATE:	DRAWING No.
- 1	Peachtree Corners, Georgia 30092	NOT TO SCALE				BACKCHECKED:		DATE:	E4 0000
- 1		NOT TO SCALE	-		-	CORRECTED:		DATE:	51.0008
- 1						VERIFIED:		DATE -	71 0000

31) SAMPLING FREQUENCY

Sampling frequency shall be according to GAR100002 IV.D.6.d. Sampling by the permittee shall occur for the following qualifying events:

(a). For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a stormwater discharge that occurs during normal business hours after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the representative sampling location;

(b). In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a stormwater discharge that occurs during normal business hours either 90 days after the first sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location selected as the representative sampling location, whichever comes first;

(c). At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours* until the selected turbidity standard is attained, or until postrain event inspections determine that BMPs are properly designed, installed and maintained;

SEDIMENT STORAGE

The Sediment Storage Table summarizes the required and available sediment storage for every outfall on this project. The Contractor shall provide and maintain the storage volumes for the BMP's specified in this table.

To prevent runoff from bypassing inlet sediment traps, a temporary sump shall be installed around all inlet sediment traps that are not located in a low point or an excavated sump. Construct temporary sumps in accordance with Construction Detail D-24C. Temporary sumps shall be installed in a manner that ensures stormwater does not bypass the inlet. The Contractor may submit alternate temporary containment berm designs to the Project Engineer for approval.

SEDIMENT STORAGE TABLE								
0.46-1110	Total Drainage	Disturbed	Required Sediment	Total Storage Volume	Tra	ediment aps /each)	Silt Fence (0.3 yd ³ /ft)	
Outfall ID	Area	Area	Storage Volume	Provided	# of Devices	Total Volume	Length	Total Volume
	(acres)	(acres)	(yd³)	(yd³)		(yd³)	(ft)	(yd³)
Outfall A	2.78	0.58	186.5	300.0	18	90.0	699.9	210.0
Outfall B	0.96	0.50	64.5	161.3	15	75.0	287.7	86.3
Total Sheet Flow	0.76	0.23	50.9	312.7	0	0.0	1042.4	312.7



GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001

Kin	nley	/»}	Hor	n
3930	Planning, A East Jones E chtree Corn	Bridge Road		ants

REV I	SION E	DATES		ESPCP GI	ENE	RAL NO	TES	
			l 1	DLEWOOD RD	ΑT	FELLO	NSHIP R	D
			CHECKED:		DATE:		DRAWIN	VG N

NOT TO SCALE

	CHECKED:	DATE:	DRAWING No.
	BACKCHECKED:	DATE:	F1 0000
	CORRECTED:	DATE:	l 51_0009
	VERIFIED:	DATE:	71-0003

ogan.Bennett

<u>DISCHARGES INTO OR WITHIN ONE LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BIOTA IMPAIRED STREAM SEGMENT</u>

The Impaired Stream Table is a summary of project outfalls within 1 mile and within the watershed of an identified impaired stream segment that has been listed for criteria violated, "Bio F" (impaired fish community) and/or "Bio M" (impaired macro invertebrate community), within Category 4a, 4b or 5, and the potential cause is either "NP" (nonpoint source) or "UR" (urban runoff).

	IMPAIRED STREAM TABLE							
Outfall ID#	Outfall Location (Station and Offset)	Reach Name	Location of the Impaired Stream Segment as Indicated in the 305b/303d List	Criteria Violated (Bio F Bio M)	Potential Cause (NP UR)	Category (4a, 4b, or 5)	Numeric waste load allocation (WLA) for sediment*	
Outfall A	STA. 108+36.27, 26.44' LT	South Fork Peachtree Creek	Headwaters to Peachtree Creek, Atlanta	Bio F Bio M	UR	4a	0.1 tons/year	
Outfall B	STA. 108+36.27, 28.42' RT	South Fork Peachtree Creek	Headwaters to Peachtree Creek, Atlanta	Bio F Bio M	UR	4a	0.1 tons/year	

The TMDL for South Fork Peachtree Creek basin was completed in December 2017. The infrastructure construction project WLA for sediment is 0.1 tons/year.

*If the TMDL Implementation Plan establishes a specific numeric waste load allocation that applies to the project discharge(s) to the Impaired Stream Segment, then the Certified Design Professional must incorporate that allocation into the ESPCP and implement all necessary measures to meet that allocation. See Appendix 1 for additional required BMP's for this project.

SOIL SERIES INFORMATION

47) The following is a summary of the soils that are expected to be found on the project site:

MAP UNIT SYMBOL	MAP UNIT NAME	RATING	COMPONENT NAME (PERCENT)	RATING REASONS (NUMERIC VALUES)	
CuC	Cecil-Urban land complex, 2 to 10 percent slopes		Cecil (65%) Urban Land (35%)	N/A	90.3%
PfC	Pacolet sandy loam, 2 to 10 percent slopes		Pacolet (100%)	N/A	4.1%
Ud	Urban land	Moderate	Urban Land (100%)	N/A	5.6%
	•			Total	100.0%



GSWCC CHECKLIST ITEM NO.
PER CHECKLIST ON 51-0001

Kimley»Horn
Engineering, Planning, And Environmental Consultants 3930 East Jones Bridge Road, Sulte 350 Peachtree Corners, Georgia 30092

	REV I .	SION E	DATES
<i>NOT TO SCALE</i>			
NOT TO SCALE			

ESPC	P G	ENE	RAL NOTES	
<i>IDLEWOOD</i>	RD	ΑT	FELLOWSHIP	RD

	CHECKED:	DATE:	DRAWING No.
	BACKCHECKED:	DATE:	
	CORRECTED:	DATE:	l 51_0010
	VERIFIED:	DATE:	1 21-0010

7/1/2025 Logan.Bennett	3:41:19 PM				
	APPENDIX 1		<u>ES</u>	SPCP SIGN	•
②22 ②3	THE ES&PC PLAN MUST INCLUDE AT LEAST FOUR (4) OF THE FO THE SITE WHICH DISCHARGE TO AN IMPAIRED STREAM SEGME APPROVED IN WRITING A REQUEST TO DISTURB 50 ACRE The four items chosen must be appropriate for the site conditions. Plan Included	ENT AND FOR SITES WHICH EPD HAS	St ir Se Se ma	ne large sign shall be in the form tandard Specification 153. Fabricants tastall the sign according to Section tection 910, Section 911, Section 9 tection 913. The cost of the sign is taintenance, and removal shall be is	te and on 636, 12, and nstallation, ncluded in
	Page # Y/N A During construction activities, double the width of the 25-foot undisturbed vegetated bundisturbed vegetated buffer along all State Waters classified as "trout streams" requivariances to any such buffers that are increased in width.	iliring a buffer. During construction activities, EPD will not grant	by or	ay item 161-1000. It shall be pos the actual start of construction n site until the end of construction coject plans must be available on	and remain on. The
	b. Increase all temporary sediment basins and retrofitted storm water management bas cubic yards) per acre drained. C. Use baffles in all temporary sediment basins and retrofitted storm water managemen the outlet structure. A large sign (minimum 4 feet x 8 feet) must be posted on site by the actual start date. The sign must identify the following: (1) construction site, (2) the permittee(s), (3) the permittee-hosted website where the Plan can be viewed and must be provided on the be available on the provided website until a NOT has been submitted.	t basins to at least double the conventional flow path length to e of construction. The sign must be visible from a public roadway. contact person(s) and telephone number(s), and (4) the submitted NOI. The sign must remain on site and the Plan must	Th pr of be ro	ebsite until a NOT has been submit ne sign shall be posted parallel to referably facing the driveway to to fice trailer. The location of the e such that it is visible and read oad. The sign must identify the fo	o a road, he field sign shall able from a ollowing:
	e. Use tackifiers and/or mulch to stabilize areas left disturbed for more than seven (7) c NPDES Permits. 51-0009 Y f. Conduct turbidity sampling after every rain event of 0.5 inch or greater within any 24-l IV.D.6.d. of the current NPDES Permits. N g. Comply with the applicable end-of-pipe turbidity effluent limit, without the "BMP defer	nour period, recognizing the exceptions specified in Part	t h ar P l	1) construction site, (2) permittene contact person(s) and telephone and (4) the permittee-hosted websited an can be viewed must be provided	number(s), e where the on the
	h. Reduce the total planned site disturbance to less than 50% impervious surfaces (exc All calculations must be included on the Plan. N i. Limit the amount of disturbed area at any one time to no greater than 25 acres or 50%.	luding any State-mandated buffer areas from such calculations).	pr "T	ubmitted NOI. For "PROJECT #" ente roject id number. For "Project Eng relephone" enter Construction Proj and their telephone number.	ineer" and
	must be included on the Plan. N j. Use "Dirt II" techniques available on the EPD website to model and manage construction must be included on the Plan. N k. Conduct soil tests representative of conditions at the time of planting to identify and to organic soil amendments (e.g., compost) and conduct pre- and post-construction soil	o implement site-specific fertilizer needs and/or add appropriate	ht	ne permittee-hosted website is: tps://www.tuckerga.gov/building_p d-roundabouts/#	rojects/idlewood-
	levels of soil carbon after final stabilization of the construction site. N I. Use mulch filter berms, in addition to a silt fence, on the site perimeter wherever constitution. Mulch filter berms cannot be placed in waterways or areas of concentrated flow.	struction storm water (including sheet flow) may be discharged.		<u> STURBED AREA STABILIZATION</u> Sturbed areas shall be stabilized	with
	N m. Use appropriate erosion control slope stabilization instead of concrete in all construction year, 24-hour rainfall event. N n. Use flocculants or coagulants under a passive dosing method (e.g., flocculant blocks that feed into temporary sediment basins and retrofitted management basins.		su of Sp	uitable material listed in the cur the Department's Standard Specif Decial Provisions) Sections 161, 10	rent edition ications (or 63, 700, or
	o. Install sod for a minimum 20-foot width (in lieu of seeding) after final grade has been a (including sheet flow) may be discharged.	achieved, along the site perimeter wherever storm water	ac	ctivities are expected to resume.	
	p. Certified personnel shall conduct inspections at least twice every seven (7) calendar inches rainfall or greater in accordance with Part IV.D.4.a.(3)(a)-(c) of this permit.	. •		DDITIONAL SITE INSPECTIONS	
	Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate compost blankets (minimum depth 1.5 inches) to protect soil s stabilization phase of the construction activity. Ropply the appropriate composition activity.	onventional BMPs as certified by a design professional (unless sing this item please refer to the Alternative BMP guidance	co (7 er gr	ertified personnel for primary perionduct inspections at least twice of the control of the control of the storm that is 0.5 inchested in accordance with Part IV.	every seven rs of the rainfall or D.4.a.(3)(a)
	calculations must be included in the Plan. N t Conduct inspections during the intermediate grading and drainage BMP phase and d professional who prepared the Plan in accordance with Part IV.A.5 of the permit. The Plan must include a statement that the primary permittee must retain the design professional who processional who	uring the final BMP phase of the project by the design	()	c); secondary permittees, Part IV. c); and tertiary permittees Part IV) (c) *	
	drainage BMP phase and during the final BMP phase. N u. Install Post Construction BMPs (e.g., runoff reduction BMPs) which remove 80% TSS known as the Blue Book, or an equivalent or more stringent design manual. * This requirement is different for infrastructure projects:	S as outlined in the Georgia Stormwater Management Manual,		* No. 39533 PROFESSIONAL	
	Certified personnel for primary permittees shall conduct inspections at least once every seven (7) calendary	ar days and within 24 hours of the end of the storm that is 0.5 inches rainfall or		7/3/2025	
	greater in accordance with Part IV.D.4.a.(3)(a) – (c) of the permit	Effective January 1, 2025		(#	# GSWCC CHECKLIST ITEM NO. PER CHECKLIST ON 51-0001
		Kimley >>> Horn Engineering, Planning, And Environmental Consultants		IDLEWOOD RD	NERAL NOTES AT FELLOWSHIP RD
GPLN-CE 11/05/2020		3930 East Jones Bridge Road, Sulte 350 Peachtree Corners, Georgia 30092	NOT TO SCALE	BACKCHECKED:	DATE: DRAWING NO. DATE: 51 - 0011

2017 rd	II:08:40 AM GPLOT-V8 gplotbord	ter-V81-P0. tb1	EC-L(sheets 1-7).dgn
CODE	PRACTICE STD OR DETAIL SPEC. SECT.	. DETAIL	DESCRIPTION
	ORANGE BARRIER FENCE		ORANGE BARRIER FENCE DELINEATES ENVIRONMENTALLY SENSITIVE AREAS WHERE THE CONTRACTOR SHALL NOT CLEAR, GRUB, OR PLACE CONSTRUCTION MATERIALS OR EQUIPMENT WITHIN THIS AREA.
	L	INE CODE	
	ORANGE	E BARRIER FENCE	
	ENVIRONMENTALLY SENSITIVE AREA		AN ENVIRONMENTALLY SENSITIVE AREA (ESA) CONTAINS RESOURCES THAT ARE ENVIRONMENTALLY, CULTURALLY, OR HISTORICALLY SENSITIVE. ESAS INCLUDE, BUT ARE NOT LIMITED TO: STATE WATER BUFFERS, HISTORIC SITES, ARCHAEOLOGICAL SITES, AND PROTECTED ANIMAL AND PLANT SPECIES HABITATS.
ESA	L	INE CODE	IF WORK IS AUTHORIZED IN THIS AREA, THE WORK MUST BE PERFORMED IN ACCORDANCE WITH SECTION 107 AND ANY OTHER APPLICABLE SPECIAL PROVISIONS AND APPLICABLE PLAN NOTES.
	ESA-25'(OR 5	50' JSTREAM BUFFER, ETC.	
	BUFFER ZONE	181	A STRIP OF UNDISTURBED ORIGINAL VEGETATION, ENHANCED OR RESTORED EXISTING VEGETATION, OR THE RE-ESTABLISHMENT OF VEGETATION SURROUNDING AN AREA OF DISTURBANCE OR BORDERING STREAMS, PONDS, WETLANDS, LAKES, AND COASTAL WATERS.
Bf		SYMBOL	WHEN NECESSARY, BUFFER ZONES ARE TO BE PROTECTED BY ORANGE BARRIER FENCE.
		Bf	
	MULCH	11 11 11 11 11 11 11 11 11 11 11 11 11	THIS IS AN APPLICATION OF STRAW MULCH USED TO REDUCE SOIL EROSION AND STABILIZE THE SOIL. IT IS USED TO CONTROL EROSION IN AREAS WHERE PERMANENT VEGETATION IS OUT OF SEASON OR TO TEMPORARILY STABILIZE AREAS PRIOR TO FINAL GRADING.
Ds I	SECTION 163	***************************************	MULCHING REQUIREMENTS ARE ADDRESSED BY STANDARD SPECIFICATIONS AND/OR THE PROJECT ENGINEER.
		SYMBOL Ds I	THE BMP SYMBOL FOR APPLICABLE AREAS AND/OR A NOTE SHALL BE INCLUDED ON APPLICABLE SHEETS IN SECTION 54.
	TENDODADY		THE SOWING OF A QUICK GROWING SPECIES OF GRASS SUITABLE TO THE AREA
	TEMPORARY GRASSING	**************************************	AND SEASON. IT IS TYPICALLY USED TO CONTROL EROSION IN AREAS LONGER THAN MULCHING IS EXPECTED TO LAST. TEMPORARY GRASSING SHOULD BE USED ON ALL PROJECTS ACCORDING TO THE
Ds2	SECTION 163,700	SYMBOL	STANDARD SPECIFICATIONS. THE BMP SYMBOL FOR APPLICABLE AREAS AND/OR A NOTE SHALL BE INCLUDED ON APPLICABLE SHEETS IN SECTION 54.
		Ds2	on the condition of the

CODE	PRACTICE STD OR DETAIL SPEC. SECT.	DETAIL	DESCRIPTION
Ds3	PERMANENT GRASSING SECTION 700	SYMBOL Ds3	THE SOWING OF PERMANENT VEGETATION, SUCH AS GRASS, SUITABLE TO THE AREA AND SEASON. PERMANENT VEGETATION SHALL BE USED ON ALL PROJECTS ACCORDING TO THE STANDARD SPECIFICATION. THE BMP SYMBOL FOR APPLICABLE AREAS AND/OR A NOTE SHALL BE INCLUDED ON APPLICABLE SHEETS IN SECTION 54.
Ds4	SODDING CONSTRUCTION DETAIL D-54 SECTION 700, 890	PATTERN DS4	THE INSTALLATION OF A SPECIES OF GRASS SODDING SUITABLE TO THE AREA AND SEASON TO PROVIDE IMMEDIATE PERMANENT VEGETATION. SODDING MAY BE SHOWN FOR HIGHLY SENSITIVE AREAS, TO IMPROVE AESTHETICS, OR FOR SPECIAL PLANTING REQUIREMENTS ON THE BASIS OF ENVIRONMENTAL COMMITMENTS OR LANDSCAPING REQUIREMENTS. THE BMP PATTERN FOR APPLICABLE AREAS AND/OR A NOTE SHALL BE INCLUDED ON APPLICABLE SHEETS IN SECTION 54.
F1-Co		SYMBOL FI-CO LYACRYLAMIDE	FLOCCULANTS AND COAGULANTS ARE USED TO SETTLE SUSPENDED SEDIMENT, HEAVY METALS, AND HYDROCARBONS (TSS) IN SLOW MOVING RUNOFF FROM CONSTRUCTION SITES FOR WATER CLARIFICATION. ANIONIC POLYACRYLAMIDES (PAM) MAY BE USED IN CONJUNCTION WITH BMPS WITHIN CHANNELS UPSTREAM OF A POST-CONSTRUCTION POND, TEMPORARY SEDIMENT BASIN, OR TEMPORARY SEDIMENT TRAP. FLOCCULANTS SHALL NOT BE USED DOWNSTREAM OF AFOREMENTIONED BMPS! FLOCCULANTS/COAGULANTS ARE TO BE SHOWN ON PLANS WITH APPLICABLE BMP IF NEEDED. PAYMENT FOR PAM AS A FLOCCULANT WILL BE INCLUDED IN THE PRICE FOR THE INSTALLATION AND/OR MAINTENANCE OF THE BMP IT IS USED IN CONJUNCTION WITH. NO SEPARATE PAYMENT WILL BE MADE.
Sb	STREAMBANK STABILIZATION SECTION 702	PATTERN Sb	STREAMBANK STABILIZATION IS THE USE OF READILY AVAILABLE NATIVE PLANT MATERIALS TO MAINTAIN AND ENHANCE STREAMBANKS, OR TO PREVENT, OR RESTORE AND REPAIR SMALL STREAMBANK EROSION PROBLEMS. STREAMBANK STABILIZATION AREAS SHOULD BE SHOWN ON THE PLANS WHEN APPLICABLE TO THE PROJECT. REFER TO THE PROJECT'S STREAM AND STREAM BUFFER MITIGATION PLANS FOR PLANT SPECIES, LOCATIONS, AND OTHER PLANTING DETAILS.

NOTE:

- I. DO NOT USE EROSION CONTROL ITEMS IN A FLOWING STREAM OR IN A TIDAL AREA BELOW HIGH TIDE.
- FOR ADDITIONAL INFORMATION ON THE DESIGN AND APPLICATION OF EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES (BMPs),
 REFER TO THE LATEST EDITION OF THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION'S, 'MANUAL FOR EROSION AND SEDIMENT
 CONTROL IN GEORGIA'.



NO SCALE

EROSION CONTROL LEGENL	TES .	/ISION DAT	RE
ENOSTON CONTINUE ELOCATE			2017
UNIFORM CODE SHEET			
SHEET I OF 7			
SHEET I UF I			


CHECKED: D. EAGLETON DATE: 01/01/16 DRAWING NO.

BACKCHECKED: DATE: 52-0001

VERIFIED: DATE:


-- F. I. No.

	10:52:37 AM GPLOT-V8 gp/otbord	er-v81-P0.1b1	EC-L(sheets 1-7), dgn					 GDS.T,
CODE	PRACTICE STD OR DETAIL SPEC. SECT.	DETAIL	DESCRIPTION	CODE	PRACTICE STD OR DETAI SPEC. SECT.	L DETAIL		DESCRIPTION
	SLOPE STABILIZATION CONSTRUCTION	Mix.	SLOPE STABILIZATION (EROSION CONTROL MATTING) IS A PROTECTIVE COVERING USED TO PREVENT EROSION AND ESTABLISH TEMPORARY OR PERMANENT VEGETATION ON STEEP SLOPES, SHORE LINES, OR CHANNELS.		STONE CHECK DAM OR SANDBAG CHECK DA		UNDERLINER. STON OUTSIDE THE CLEAR	ARE CONSTRUCTED OF TYPE-3 RIP-RAP WITH GEOTEX E CHECK DAMS ARE PREFERRED IN ROADWAY DITCHES ZONE. CONSIDERATION SHOULD BE GIVEN TO USIN CHECK DAWS AND/OR BMPs WITHIN THE CLEAR ZONE
Ss	DETAIL D-35 SECTION 716	PATTERN	SLOPE STABILIZATION MAY BE A ROLLED EROSION CONTROL PRODUCT (RECP) OR A HYDRAULIC EROSION CONTROL PRODUCT (HECP). SLOPE STABILIZATION SHALL BE USED ON ALL CUT OR FILL SLOPES OF 2.5:1 OR STEEPER AND WITHIN 50 FEET OF ALL CROSS DRAINS AND	Cd-S	CONSTRUCTION DETAIL D-56 SECTION 163, 603	SYMBOL	TEMPORARY VELOCIT PROPERLY STABILIZ	S ARE RECOMMENDED IN CONCRETE LINED CHANNELS Y CONTROL ONLY. ENSURE DISCHARGE POINT IS ED AND INCLUDE APPROPRIATE BMPS FOR SEDIMENT AND/OR DOWNSTREAM OF CONCRETE LINED CHANNELS.
	X X	\$\frac{1}{5s}\$	CULVERTS. NOTE: ONLY COCONUT FIBER BLANKET OR WOOD FIBER BLANKET SHALL BE USED AS SLOPE STABILIZATION WITHIN BUFFERED AREAS.			(Cd-S)	WITHOUT A SEDIMEN	SED IN AN AREA WITH FLOWS GREATER THAN 2.0-CF T BASIN, A MINIMUM OF ONE ROCK FILTER DAM SHA TREAM DISCHARGE POINT.
	TACKIFIERS		TACKIFIERS HYDRATE IN WATER AND READILY BLEND WITH OTHER SLURRY MATERIALS AND ARE USED TO TIE-DOWN FOR SOIL, COMPOST, SEED, STRAW, HAY OR MULCH.		VEGETATED CHANNE STABILIZATION	L		CHANNEL MAY BE LINED WITH PERMANENT VEGETAT ES UP TO 5.0 fps. THIS MEASURE SHALL BE DANCE WITH THE GDOT CHANNEL LINING DESIGN PRO N CONTROL MEASURES MAY BE REQUIRED.
Tac	SECTION 163. 700, 895	Ku.	TACKIFIERS REQUIREMENTS, SUCH AS ANIONIC POLYACRYLAMIDES (PAM) ARE ADDRESSED BY STANDARD SPECIFICATIONS AND ARE NOT TYPICALLY SHOWN OF THE PLANS. PAM IS TYPICALLY USED BY THE CONTRACTOR FOR TEMPORARY OR PERMANENT GRASSING.	Ch-1	<i>1</i> 1		TYPICALLY NOT SHO	
	PO	SYMBOL Tac LYACRYLANIDE	REFER TO THE LATEST EDITION OF THE "MANUAL FOR EROSION AND SEDIMEN CONTROL IN GEORGIA" FOR CRITERIA.	T		LINE CODE	í.	
	FABRIC CHECK DAM CONSTRUCTION	TACIT ENITED	A CHECK DAW COWPOSED OF SYNTHETIC FIBER FABRIC. WIRE REINFORCED. POST, OVERFLOW WEIR, AND TURF REINFORCEMENT MATTING (TRM) SPLASHPY PLACED IN DITCHES IN A SPECIAL COMFIGURATION WHICH CONTROLS EMERGY DISSIPATION AND FILTRATION OF STORM WATER. SEE CONSTRUCTION DETAIL	γ	CHANNEL STABILIZATION RIP-RAP, TYPE I		THICK (UNLESS SPE UNDERLINER. THE R DEPTH "Dp" RECOMM	S OF LINING A CHANNEL WITH TYPE I RIP-RAP 24 CIFIED OTHERWISE) PLACED ON TOP OF A GEOTEXT IIP-RAP SHALL PROTECT THE CHANNEL FLOWING TO ENDED BY THE GDOT CHANNEL LINING PROGRAM.
(Cd-F)	DETAIL D-24D SECTION 171	D-24D FOR ADDITIONAL INFORMATION AND SPACING REQUIREMENTS. THIS ITEM IS SUITABLE FOR USE IN ROADSIDE DITCHES THAT ARE PART OF INFRASTRUCTURE CONSTRUCTION PROJECTS AND WITHIN THE CLEAR ZONE.	Ch-2R	/ 1	LINE CODE	*Dp" SHALL BE IDE	N CONTROL MEASURES MAY BE REQUIRED. NTIFIED IN A TABLE LOCATED ON THE SUMMARY OF	
		SYMBOL (cd-F)	IF THIS ITEM IS USED IN AN AREA WITH FLOWS GREATER THAN 2.0-CFS OF WITHOUT A SEDIMENT BASIN. A MINIMUM OF ONE ROCK FILTER DAM SHALL EUSED AT THE DOWNSTREAM DISCHARGE POINT.	R BE		LINE CODE	POLLUTION CONTROL	AND IN THE EROSION, SEDIMENTATION, AND PLAN.
	COMPOST FILTER SOCK CHECK DAM		A COMPOST FILTER SOCK CHECK DAM IS COMPOSED OF A PHOTODEGRADABLE OBIODEGRADABLE KNITTED MESH MATERIAL CONTAINING A WEED FREE FILLER MATERIAL DERIVED FROM A WELL-DECOMPOSED SOURCE OF ORGANIC MATTER. THEY SHALL BE PROPERLY STAKED FOR DITCH APPLICATIONS.	DR	CHANNEL STABILIZATION RIP-RAP, TYPE 3		THICK (UNLESS SPE	S OF LINING A CHANNEL WITH TYPE 3 RIP-RAP 24 CIFIED OTHERWISE) PLACED ON TOP OF A GEOTEXT IP-RAP SHALL PROTECT THE CHANNEL FLOWING TO ENDED BY THE GDOT CHANNEL LINING PROGRAM.
(Cd-Fs)	CONSTRUCTION DETAIL D-52 SECTION 163		REFER TO THE LATEST EDITION OF THE "MANUAL FOR EROSION AND SEDIMEN CONTROL IN GEORGIA" FOR MATERIAL SPECIFICATIONS.	(Ch-2R3	CONSTRUCTION DETAIL D-49 SECTION 603		ADDITIONAL EROSIO	N CONTROL MEASURES MAY BE REQUIRED. NTIFIED IN A TABLE LOCATED ON THE SUMMARY OF
		SYMBOL (Cd-Fs)	IF THIS ITEM IS USED IN AN AREA WITH FLOWS GREATER THAN 2.0-CFS OR WITHOUT A SEDIMENT BASIN. A MINIMUM OF ONE ROCK FILTER DAM SHALL BUSED AT THE DOWNSTREAM DISCHARGE POINT.	BE CONTRACTOR		LINE CODE		AND IN THE EROSION, SEDIMENTATION, AND
	BALED STRAW CHECK DAM CONSTRUCTION DETAIL D-52		A BALE STRAW CHECK DAW IS COMPOSED OF BALES PREFERABLY BOUND WITH WIRE OR NYLON INSTEAD OF TWINE. BALES SHOULD BE PLACED IN ROWS WI BALE ENDS TIGHTLY ABUTTING ADJACENT BALES. THE DOWNSTREAM ROW OF BALES SHALL BE PLACED IN A TRENCH TO ALLOW THE TOP OF THE BALE LONG, WIDE SIDE TO BE LEVEL WITH THE GROUND AS A NON-ERODIBLE SPLAPAD. PROPER STAKING IS ALSO REQUIRED FOR DITCH APPLICATIONS.	NOTE:	EDOCION CONTDOL ITEM	S IN A FLOWING STREAM O	DD IN A TIDAL AREA DEL	ON HICH TIDE
(СО-НЬ)	SECTION 163	SYMB0L (Cd-Hb)	IF THIS ITEM IS USED IN AN AREA WITH FLOWS GREATER THAN 2.0-CFS OR WITHOUT A SEDIMENT BASIN. A MINIMUM OF ONE ROCK FILTER DAM SHALL BUSED AT THE DOWNSTREAM DISCHARGE POINT.	2. FOR ADDITION	DNAL INFORMATION ON TI IE LATEST EDITION OF T	HE DESIGN AND APPLICATI	ON OF EROSION AND SEL	DIMENT CONTROL BEST MANAGEMENT PRACTICES (E ISSION'S, "MANUAL FOR EROSION AND SEDIMENT
						3/2/20	REVISION DATES	EROSION CONTROL LEGEND
			GE	7-1	NO SC	11/28/2		UNIFORM CODE SHEET SHEET 2 OF 7 ECKED: [D. EAGLETON [DATE:]01/01/16] DRA
					110 00		BA	CKCHECKED: DATE: 01/01/16 DRA CKCHECKED: DATE: 5) ORBECTED: DATE: 5)





DRAWING No.


BACKCHECKED





	//:/0:19 AM	EC-L(sheets 1-7). dgn			GB S:1,
CODE	PRACTICE STD OR DETAIL DETAIL SPEC. SECT.	DESCRIPTION	CODE	PRACTICE STD OR DETAIL DETAIL SPEC. SECT.	DESCRIPTION
Fr	CONSTRUCTION DETAIL D-46 SECTION 163 SYMBOL FILTER RING SYMBOL	A TEMPORARY STONE BARRIER CONSTRUCTED AT DRAINAGE STRUCTURE INLETS AND POST-CONSTRUCTION POND OUTLETS. IT REDUCES RUNOFF VELOCITY AND HELPS PREVENT SEDIMENT FROM LEAVING SITE PRIOR TO PERMANENT STABILIZATION OF THE DISTURBED AREA. REFER TO THE LATEST EDITION OF THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR ADDITIONAL INFORMATION ON USAGE.	(Rt-B)	RETROFITTING SLOTTED BOARD DAM CONSTRUCTION DETAIL D-45 SECTION 163 SYMBOL R1-B	A SLOTTED BOARD DAW CONSISTS OF STONE AND/OR FILTER FABRIC AND BOARDS WITH 0.5' - 1.0' SPACING TO SERVE AS A TEMPORARY SEDIMENT FILTER. PERMANENT STORMWATER DETENTION POND OUTLET: -DRAINAGE AREA UP TO 100 ACRES -DETENTION BASINS LARGE ENOUGH TO STORE 67 CUBIC YARDS OF SEDIMENT PER ACRE OF DISTURBED AREA ROADWAY DRAINAGE STRUCTURE: -OPEN END PIPES, WINGED HEADWALLS, OR CONCRETE WEIR OUTLETS WITH DRAINAGE AREA LESS THAN 30 ACRES REFER TO THE LATEST EDITION OF THE 'MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA' FOR DESIGN CRITERIA.
Rd	ROCK FILTER DAM CONSTRUCTION DETAIL D-43 SECTION 163, 603 SYMBOL	ROCK FILTER DAMS ARE CONSTRUCTED OF TYPE 3 STONE RIP-RAP FACED WITH *57 STONE ON THE UPSTREAM SIDE. THEY ARE PLACED ACROSS DRAINAGEWAYS WHICH DRAIN 50 ACRES OR LESS. GEOTEXTILE UNDERLINER SHALL BE USED WHEN PLACING ROCK FILTER DAMS. THE DAM SHOULD NOT BE HIGHER THAN THE CHANNEL BANKS. ROCK FILTER DAMS SHOULD BE USED IN DITCHES PRIOR TO DISCHARGING INTO STREAMS, WETLANDS, OPEN-WATERS, OR OTHER ESAS.	Rt-Sg1 Rt-Sg2 Rt-Sg3	RETROFITTING SILT CONTROL GATES CONSTRUCTION DETAIL D-20 SECTION 163 SYMBOL Rt-Sg1 Rt-Sg2 Rt-Sg3	A SILT CONTROL GATE CONSISTS OF BOARDS WITHOUT SPACING AND FILTER FABRIC TO BE USED FOR TEMPORARY SEDIMENT STORAGE ON ROADWAY PROJECTS AT THE INLET OF STRUCTURES WITH A DRAINAGE AREA UP TO 50 ACRES. THE DISTURBED AREA WITHIN THE DRAINAGE AREA SHALL NOT EXCEED 5 ACRES. SILT CONTROL GATES SHOULD NOT BE USED ALONE, BUT WITH ANOTHER BMP DOWNSTREAM PRIOR TO DISCHARGE LEAVING PROJECT ARD NOT USE SILT GATES IN STATE WATERS. Rt-SgI=TYPE I: USED ON BOX CULVERTS Rt-Sg2=TYPE 2: USED ON STRAIGHT HEADWALLS Rt-Sg3=TYPE 3: USED ON FLARED END SECTIONS AND TAPERED HEADWALLS
Rd-B	STONE FILTER BERM CONSTRUCTION DETAIL D-50 SECTION 163, 603 LINE CODE	STONE FILTER BERMS ARE CONSTRUCTED SIMILAR TO ROCK FILTER DAMS FOR A LINEAR APPLICATION. THEY ARE CONSTRUCTED OF TYPE-3 STONE RIP-RAP FACED WITH *57 STONE ON THE UPSTREAM SIDE. GEOTEXTILE UNDERLINER SHALL BE USED WHEN PLACING STONE FILTER BERMS. STONE FILTER BERMS ARE IDEAL ALONG THE PERIMETER FOR SHEET FLOW AND/OR SHALLOW CONCENTRATED FLOW TO A COMMON LOW AREA WHERE PERIMETER SILT FENCE ALONE MAY BE INSUFFICIENT, THERE IS NO WELL-DEFINED CHANNEL FOR A STANDARD ROCK FILTER DAM, AND/OR CONSTRUCTING A ROCK OUTLET TEMPORARY SEDIMENT TRAP IS NOT APPLICABLE.	(Sd1-NS)	SEDIMENT BARRIER (NON-SENSITIVE) SILT FENCE TYPE A CONSTRUCTION DETAIL D-24 SECTION 171 LINE CODE -A-A-A-A-SILED-A-A-A-A-A-A-A-A-A-A-A-A-A-A-A-A-A-A-A	SEDIMENT BARRIERS MINIMIZE AND PREVENT SEDIMENT CARRIED BY SHEET FLOW FROM LEAVING THE PROJECT AREA BY CAUSING DEPOSITION AND/OR FILTRATION OF SEDIMENT. SILT FENCE USED AS PERIMETER CONTROL SHA NOT BE INSTALLED ACROSS CONCENTRATED FLOW. TYPE-A SILT FENCE IS TYPICALLY USED IN NON-ENVIRONMENTALLY SENSITIVE AREAS (ESAS) OR IN AREAS WITH FILLS LESS THAN 10'. IT SHOULD BE PLACED A MINIMUM OF 10' FROM CONSTRUCTION LIMITS OR ALONG THE RIGHT-OF-WAY LINE.
Rp	SECTION 603 PATTERN Rp	RIP-RAP IS A FLEXIBLE PERMANENT BLANKET FOR PROTECTION OF FILL SLOPES AND BRIDGE END ROLLS. RIP-RAP TYPE-I SHOULD BE PLACED ON TOP OF A GEOTEXTILE UNDERLINER AT A MINIMUM 24' THICKNESS OR AS INDICATED ON THE PLANS. RIP-RAP MAY ALSO BE USED AT DRAINAGE STRUCTURE OUTLETS WITHIN THE RIGHT-OF-WAY. HOWEVER, APPROPRIATE OUTLET PROTECTION SHOULD BE PROVIDED AT OUTFALLS. REFER TO STORM DRAIN OUTLET PROTECTION FOR ADDITIONAL INFORMATION ON USING RIP-RAP AT OUTFALLS.	(Sd1-S)	SEDIMENT BARRIER (SENSITIVE) SILT FENCE TYPE C CONSTRUCTION DETAIL D-24 SECTION 171 LINE CODE -c -c -c - SII-S - c - c - c -	SEDIMENT BARRIERS MINIMIZE AND PREVENT SEDIMENT CARRIED BY SHEET FLOW FROM LEAVING THE PROJECT AREA BY CAUSING DEPOSITION AND/OR FILTRATION OF SEDIMENT. SILT FENCE USED AS PERIMETER CONTROL SHANOT BE INSTALLED ACROSS CONCENTRATED FLOW. TYPE-C SILT FENCE IS TYPICALLY USED IN ENVIRONMENTALLY SENSITIVE AREAS (ESAs) OR IN AREAS WITH FILLS 10' AND GREATER. ALL ENVIRONMENTALLY SENSITIVE AREAS (ESAs) SHALL BE PROTECTED WITH A DOUBLE-ROW OF TYPE-C SILT FENCE REGARDLESS OF FILL HEIGHT. A SINGLE-ROW MAY BE USED FOR OTHER APPLICATIONS. IT SHOULD BE PLACED A MINIMUM OF 10' FROM CONSTRUCTION LIMITS OR ALONG THE RIGHT-OF-WAY LINE.
Rt-P	RETROFITTING PERFORATED HALF-ROUND PIPE CONSTRUCTION DETAIL D-44 SECTION 163 SYMBOL R1-P	A PERFORATED HALF-ROUND PIPE WITH STONE FILTER PLACED IN FRONT OF A PERMANENT STORMWATER DETENTION POND OUTLET STRUCTURE TO SERVE AS A TEMPORARY SEDIMENT FILTER. SHOULD BE USED ONLY IN DETENTION PONDS WITH LESS THAN 30 ACRES TOTAL DRAINAGE AREA. SHALL ONLY BE USED IN DETENTION BASINS LARGE ENOUGH TO STORE 67 CUBIC YARDS OF SEDIMENT PER ACRE OF DISTURBED AREA. REFER TO THE LATEST EDITION OF THE 'MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA' FOR DESIGN CRITERIA.	2. FOR ADDITIONAL	ATEST EDITION OF THE GEORGIA SOIL AND WATE	IN A TIDAL AREA BELOW HIGH TIDE. I OF EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES (BMPs R CONSERVATION COMMISSION'S, "MANUAL FOR EROSION AND SEDIMENT
		65) - ,	NO SCALE	EROSION CONTROL LEGEND UNIFORM CODE SHEET SHEET 5 OF 7 CHECKED: D. EAGLETON DATE: 01/01/16 DRAWING NO BACKCHECKED: DATE: 52 - 0 0 0 5












































































SINGLE ROW TYPE C SILT FENCE WITH HIGH TENSILE POLYPROPYLENE INTEGRATED SUPPORT WOVEN FABRIC





SINGLE ROW TYPE A SILT FENCE


	GDQT Geographen of Temperaturiation	P.I. 169.
MAX SPACING 4' O.C.	о в попровення	
TOP AND BOTTOM WIRE MIN.10 GAUGE		
APPROVED FILTER FABRIC WOVEN WIRE 12/2GAUGE 12/2GAUGE 12/2GAUGE MAX MESH SUPPORT GROUND LINE STEEL POST (SEE SECTION 171)	APPROVED FABR STEEL OR W (SEE SECTION	H
WOVEN WIRE SUPPORTED POLYF	PROPYLENE MESH SUPPORT TYPE C FENCE	
POLYPROPYLENE MESH OR WOVEN WIRE FENCE (BETWEEN POST & FILTER FABRIC) APPROVED FILTER FABRIC SLOPI ** THE TOTA SHALL BE VERTICAL	E L WIDTH OF THE FILTER F. 3' MIN. AND WOULD INCLUD WIDTH AND 2" OF TOE.	
SINGLE ROW TYPE C SILT FENCE WITH WO' OR POLYPROPYLENE MESH SL	VEN WIRE SUPPO JPPORT	ORT


FENCE TYPE	POST LENGTH	Н	D	W*	TYPICAL USES
TYPE "A"	4 FT.	2'-4"	1′-6"	3′-0"	
TYPE "C"	4 FT.	2'-4"	1′-6"	3′-0"	AT BRIDGE END ROLLS, DOUBLE ROW ALONG STREAMS, WETLANDS AND ENVIRONMENTALLY SENSITIVE AREAS FOR USE OF THIS MATERIAL IN FABRIC CHECKDAMS SEE D-24D.


NOTES

- 1. WIRE STAPLES SHALL BE AT LEAST 17 GAUGE, WITH LEGS AT LEAST $\frac{1}{2}$ INCHES LONG AND A CROWN AT LEAST $\frac{3}{4}$ INCHES WIDE. NAILS SHALL BE AT LEAST 14 GAUGE, I INCH LONG , WITH BUTTON HEADS AT LEAST $\frac{3}{4}$ INCHES WIDE.
- 2. SEE SECTION 171 FOR PLACEMENT OF NAILS OR STAPLES FOR TYPE A AND TYPE C FENCES.
- 3. THE VERTICAL WIRES FOR THE WOVEN WIRE SUPPORT FENCE SHALL HAVE A MAXIMUM SPACING OF 12 INCHES. THE TOP AND BOTTOM WIRES SHALL BE AT LEAST 10 GAUGE AND ALL OTHER WIRES SHALL BE AT LEAST $12\frac{1}{2}$ GAUGE.
- 4. TEMPORARY SILT FENCE INSTALLATION IS DIFFERENT THAN THE SILT RETENTION BARRIER INSTALLATION.
- 5. SEE SECTION 171 FOR SILT FENCE SPECIFICATIONS.
- 6. SEE SECTION 894 FOR FENCING SPECIFICATIONS.
- 7. SEE QPL-36 FOR A LIST OF APPROVED SILT FENCE FABRIC.
- 8. TEMPORARY SILT FENCE SHALL NOT BE PLACED WITHIN STATE WATERS UNLESS PERMITTED.


09-2022	DATE	DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA
ADDED HIGH TENSILE POLYPROPYLENE INTEGRATED FARRIC	1 1	CONSTRUCTION DETAIL TEMPORARY SILT FENCE
AL	ВУ	JANUARY 2011 NUMBER D-24A







ENTRANCE ELEVATION



- AVOID LOCATING CONSTRUCTION EXITS ON STEEP SLOPES OR AT SHARP CURVES ON PUBLIC ROADS. CONSTRUCTION EXITS ARE NOT REQUIRED FOR DIRT PUBLIC ROADS.
- REMOVE ALL VEGETATION AND OTHER UNSUITABLE MATERIAL FROM THE FOUNDATION AREA AND GRADE FOR POSITIVE DRAINAGE.
- AGGREGATE SIZE SHALL BE COARSE NO. 3 AGGREGATE WITH 0.0% PASSING THE 1.06 INCH U.S. STANDARD SIEVE.
- GRAVEL PAD SHALL HAVE A MINIMUM THICKNESS OF 6 INCHES AND PLACED ON APPROVED PLASTIC FILTER FABRIC.
- GRAVEL PAD WIDTH SHALL BE EQUAL FULL WIDTH AT ALL POINTS OF VEHICULAR EGRESS, BUT NO LESS THAN 20'.
- PROVIDE A TRAVERSABLE DIVERSION RIDGE CONSTRUCTED OF AGGREGATE 6 INCHES TO 8 INCHES HIGH WHEN GRADE TOWARD PAVED AREA IS GREATER THAN 2%.
- INSTALL CULVERT UNDER THE ENTRANCE IF NEEDED TO MAINTAIN DRAINAGE DITCHES.

GENERAL NOTES:

- TIRE WASH AREA INCLUDES SEDIMENT TRAP OR OTHER ACCEPTABLE SEDIMENT STORAGE DEVICE AND SHALL BE CONSTRUCTED EVEN IF CONSTRUCTION EXIT TIRE CLEANING STATION IS NOT USED.
- IF THE ACTION OF THE VEHICLE TRAVELING OVER THE GRAVEL PAD DOES NOT SUFFICIENTLY REMOVE THE MUD PRIOR TO ENTERING PUBLIC ROADS THUS DICTATING ADDITIONAL TIRE CLEANING MEASURES, THE CONTRACTOR SHALL ADD A CONSTRUCTION EXIT TIRE CLEANING STATION TO AN EXISTING CONSTRUCTION EXIT OR WHEN DIRECTED BY THE ENGINEER. THE CONSTRUCTION EXIT TIRE CLEANING STATION INCLUDES: WATER SOURCE, LABOR AND ALL MATERIALS NECESSARY TO PERFORM TASK. THIS WILL BE PAID FOR AS SHOWN IN SECTION 163.

THE WASHING SHALL BE DONE ON AN AREA STABILIZED WITH AGGREGATE THAT DRAINS INTO A SEDIMENT TRAP OR OTHER ACCEPTABLE SEDIMENT STORAGE DEVICE. DIVERT ALL SURFACE RUNOFF AND DRAINAGE FROM THE CONSTRUCTION EXIT TO THE SEDIMENT CONTROL DEVICE. ACCEPTABLE SEDIMENT STORAGE DEVICE EXAMPLES INCLUDE TEMPORARY SEDIMENT TRAPS, HAY BALES OR STONE FILTER RING WITH THE SEDIMENT STORAGE SIZED FOR 67 CUBIC YARDS PER ACRE OF DRAINAGE. TIRE WASHING SHALL BE DONE MANUALLY OR BY EQUIPMENT SUITABLE FOR TRUCK TRAFFIC THAT REMOVES MUD AND DIRT.

- AGGREGATE SHALL BE KEPT LOOSE OR SCARIFIED WHEN AGGREGATE BECOMES CONSOLIDATED.
- CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION THAT PREVENTS TRACKING AND/OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR, AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT. MAINTENANCE OF CONSTRUCTION EXIT MAY BE PAID WITH OR WITHOUT THE MAINTENANCE OF CONSTRUCTION EXIT TIRE WASH AREA. WHEN DIRECTED BY THE ENGINEER. ALL MUD AND DEBRIS SPILLED, DROPPED. WASHED, OR TRACKED FROM VEHICLES OR SITE ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.


SEE SECTION 163 FOR THE CONSTRUCTION AND REMOVAL OF CONSTRUCTION EXITS. SEE SECTION 165 FOR THE MAINTENANCE OF CONSTRUCTION EXITS.

PAY ITEM:		
163-0301	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	(EA)
165-0101	MAINTENANCE OF CONSTRUCTION EXIT	(EA)
165-0310	MAINTENANCE OF CONSTRUCTION EXIT TIRE WASH AREA	(EA)
PAY ITEM:	FOR FIELD USE ONLY ACCORDING TO SECTION 163	
163-0310	CONSTRUCTION EXIT TIRE CLEANING STATION	(DAY)

11-04-20		04-18-18	04-22-16	01-19-11	DATE	DEPAF	RTMENT OF TRANSPORTATION STATE OF GEORGIA
=-8 #	DESCS/REFS		MANUAL	LABELS			CONSTRUCTION DETAILS
GEN NOTES	ITEM	TIRE WASH &	GSWCC 2016	CONSTR. EXIT	REVISION		CONSTRUCTION EXIT
REV GE	REV PAY	REV. TII	REV. GS	REV. CC		NO SCALE	FEBRUARY 2001
HAC		DLE	DLE	TPC	ВУ	DESIGNED DRAWN _DLE_ TRACED CHECKED	NUMBER D-41


STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS	
GA.				

SOD LAYOUT




NOTE: SOD MAY BE EITHER 12" WIDE BY 22" LONG BLOCKS OR 21" WIDE BY 52' LONG ROLLS.

ABUTTING SOD



SOD APPEARANCE



GENERAL NOTES:


- I. SOD SHALL MEET SECTIONS 700 AND 890 OF THE STANDARD SPECIFICATIONS AND SUPPLEMENTS THERETO.SOD SHALL BE CUT INTO 12*W×22*L BLOCKS OR 21*W×52*L ROLLS.
- 2. PLACE SOD IN A STAGGERED PATTERN ENSURING FIRM CONTACT WITH THE SOIL. BUTT THE STRIPS TIGHTLY AGAINST EACH OTHER WITH THE AUTOMATIC SOD CUTTER ANGLES CORRECTLY MATCHED WITHOUT SPACES OR OVERLAP.
- 3. PLACE THE LONG SIDE OF SOD PERPENDICULAR TO DRAINAGE FLOW IF INSTALLED IN DITCHES.
- 4. STAKE SOD PLACED IN DITCHES OR SLOPES STEEPER THAN 2:10R ANY OTHER AREAS WHERE SOD SLIPPING MAY OCCUR. USE WOOD STAKES THAT ARE A MINIMUM OF 8*LONG AND A MAXIMUM OF I* WIDE. DRIVE STAKES FLUSH WITH THE TOP OF SOD AND USE A MINIMUM OF 8 STAKES PER SQUARE YARD TO HOLD SOD IN PLACE.
- 5. ROLL SOD IMMEDIATELY TO ACHIEVE FIRM CONTACT WITH THE SOIL.
- 6. WATER THE SOD IMMEDIATELY AFTER INSTALLATION AND WATER TO A DEPTH OF 4" AS NEEDED.
- 7. MOW ESTABLISHED SOD TO A HEIGHT NOT LESS THAN 2"-3" AS NECESSARY.

PAY ITEM: 700-9300 SOD (SY)


	DATE	DEPARTMENT OF TRANSPORT	TATION			
CONSTRUCTION DETAILS						
	REVISION	SOD INSTALLATION				
		NO SCALE	4-22-2016			
	ВУ	DESIGNED DEE TRACED CHECKED CHECKED	NUMBER D-54			

56-0004


OUTLET PERPENDICULAR TO WELL-DEFINED CHANNEL



OUTLET TO FLAT AREA



PROFILE VIEW



PROFILE VIEW

WIDTH

GENERAL NOTES:

- I. RIPRAP OUTLET PROTECTION SHOULD BE USED TO REDUCE A DRAINAGE STRUCTURE'S DISCHARGE VELOCITY.
 RIPRAP OUTLET PROTECTION IS SHOWN FOR GEORGIA STANDARD 1120, BUT IS INSTALLED SIMILARLY FOR OTHER DRAINAGE OUTLET STRUCTURES.
- 2. RIPRAP OUTLET PROTECTION SHALL BE DESIGNED IN ACCORDANCE WITH THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA".
 THE DESIGNER SHALL PROVIDE THE FOLLOWING IN THE PLANS: PIPE DIAMETER (Do), FLOW RATE OF DESIGN STORM (O), VELOCITY (V), TAILWATER
 CONDITION (Tw), APRON LENGTH (Ld), APRON WIDTH AT DRAINAGE STRUCTURE (WI), APRON WIDTH DOWNSTREAM (W2), AVERAGE STONE DIAMETER (d50),
 INSTALLATION DEPTH (D), AND TYPE OF RIPRAP WITH QUANTITY.

THE MINIMUM DESIGN FOR RIPRAP OUTLET PROTECTION SHALL BE THE 25-YEAR STORM EVENT, BUT LARGER STORMS ARE RECOMMENDED.

- 3. THE APRON WIDTHS SHALL BE THE SAME WHEN THE DRAINAGE STRUCTURE DISCHARGES PERPENDICULAR INTO A WELL-DEFINED CHANNEL.
 THE LENGTH SHALL EXTEND ACROSS THE CHANNEL AND UP TO THE TOP OF THE CHANNEL BACKSLOPE OR 1-FOOT ABOVE THE NORMAL DEPTH OF
 THE CHANNEL'S DESIGN STORM (WHICHEVER IS LESS). THE DESIGNER SHALL PROVIDE THE DEPTH OF PROTECTION (Dp) IF THE APRON DOES NOT
 EXTEND TO THE TOP OF THE BACKSLOPE.
- 4. IF THE OUTLET HYDRAULICS REQUIRE A d50<=0.70 FEET, TYPE-3 RIPRAP MAY BE USED.
 IF THE OUTLET HYDRAULICS REQUIRE A d50<=1.20 FEET, TYPE-I RIPRAP SHOULD BE USED.
 IF THE OUTLET HYDRAULICS REQUIRE A d50>1.20 FEET, THE DESIGNER SHALL DESIGN AND PROVIDE A SPECIAL DETAIL FOR APPROPRIATE OUTLET PROTECTION.
- 5. PLASTIC FILTER FABRIC IS REQUIRED UNDERNEATH RIPRAP APRON.
- 6. PAYMENT FOR RIPRAP SHALL BE MEASURED IN SQUARE YARDS FOR SPECIFIED INSTALLATION DEPTH. PAYMENT FOR PLASTIC FILTER FABRIC SHALL BE MEASURED IN SQUARE YARDS CONSISTENT WITH RIPRAP QUANTITY AND PAID FOR SEPARATELY.

Do = PIPE DIAMETER

Q = DESIGN STORM FLOW RATE

= DESIGN STORM VELOCITY

Tw = TAILWATER CONDITION/DESIGN STORM NORMAL DEPTH

La = APRON LENGTH

WI = APRON WIDTH UPSTREAM
W2 = APRON WIDTH DOWNSTREAM
d50 = AVERAGE STONE DIAMETER

D = INSTALLATION DEPTH
Dp = DEPTH OF PROTECTION

RIPRAP TYPE	REQUIRED d50 (FT)	MIN. DEPTH "D" (IN)
1	≤1.20	36
3	≤0.67	18

		DATE	DEPAR	TMENT OF TRANSPORT	TATION
			CC	INSTRUCTION DETAIL	.S
		REVISION	RI	PRAP OUTLET PROTECTION (SHEET I OF 2)	N
			NO SCALI	Ē	4-22-2016
		ВҮ	DESIGNED DLE DRAWN DLE TRACED CHECKED		NUMBER D-55A

56 - 0005