

CITY OF TUCKER

ACKNOWLEDGE RECEIPT OF ADDENDUM #2

Publish Date: January 23, 2026

ITB 2026-002

STORMWATER SYSTEM REPAIR PROJECTS

Please complete this page and include this page only in bid submittal.

**I hereby acknowledge receipt of the supplement pertaining to the
above referenced bid.**

COMPANY NAME: _____

CONTACT PERSON: _____

ADDRESS: _____

CITY: _____ **STATE:** _____ **ZIP:** _____

PHONE: _____ **FAX:** _____

EMAIL ADDRESS: _____

SIGNATURE

DATE

ITB 2026-002

ADDENDUM #2

	QUESTION	ANSWER
1	At the 3476 Canadian Way site, one of the pipes shown on the map as requiring spin cast rehabilitation has already been replaced with new CMP. Can the Owner please review the map and the scope/bid form and confirm which pipe segments are intended to receive spin cast?	The city wants to spin cast the new CMP pipe to extend its service life at the outset of its installation.
2	The Task Order file containing the videos included in the ITB documents did not open and returned a “404 File Not Found” error. Can a new link to the videos be provided?	See Addendum #1 posted on the City of Tucker Website under ITB 2026-002.
3	Can the Owner please confirm if there are any DBE Requirements or good faith efforts to complete for this project?	There is no DBE requirement for this project.
4	During my site visit for this project, I noticed that the line segment between S23811 & S10981 and 20 lf out of S10981 going towards S10986 has been recently replaced. Is the intent to Spin Cast the new pipes as part of this project?	The city wants to spin cast the new CMP pipe to extend its service life at the outset of its installation.
5	What thickness will be required on these pipes?	1.5” minimum for 60” diameter pipe, 2.0” minimum for 72” diameter pipe.
6	Will the Owner please provide the budget for this project?	The City does not reveal project budgets during the procurement process.
7	Will the Owner please provide a copy of the current plan holders list?	The City does not require bid intent reporting, therefore, no plan holder list can be provided.
8	Will the Owner please provide the anticipated NTP date for this project?	The city projects to award this contract at the March 9, 2026 council meeting, so the NTP can be issued as early as March 16, 2026.
9	Will the Owner confirm any DBE requirements for this project?	There are no DBE requirements for this project.
10	Will the Owner provide a disposal site for pipe cleaning debris at no cost to the Contractor?	No, the cost shall be factored into your unit price proposal for unit line items 39.9 and/or 41.2

ITB 2026-002

ADDENDUM #2

11	If the lowest responsible bidder's total is above the Owner's budget, are additional funds available to award?	Per the bid documents, "the city of Tucker reserves the right to reject any and all bids, or any part, to waive any formalities, to make an award and to readvertise in the best interest of the city."
12	During our site visit, we discovered that the line running from 23811 to S10981 seemed to be newly installed. We were unable to access the line running from S1098 to S10986. The link provided in Addendum 1 to previously taken video files is nonoperational. Will the Owner provide any prior video footage or information about the condition of this line, including how long ago it was installed?	The city wants to spin cast the new CMP pipe to extend its service life at the outset of its installation. Please refer to the link in addendum #1 for those background files.
13	During our visit to the Antelope Ln site, we discovered invert damage and a void running under the pipe that will likely need to be repaired to effectively rehabilitate the pipe. To ensure that bidders include this consideration in their bids and to prevent unforeseen change orders, will the Owner include a line item for void repair as measured by Cubic Yards (CY)?	It is the city's intention that this work would be conducted under line item 19.8.
14	<p>1. The current bid schedule does not include liner thickness for Geopolymer items. Will the Owner update the bid schedule as follows to confirm all Bidders are pricing items 'apples to apples'?</p> <p>60"Dia., 1.50" Minimum 72" Dia., 2.00" Minimum</p>	<p>There shall be no substitution to spin cast material.</p> <p>The minimum thickness shall be 1.5" for 60" diameter pipe and 2.0" for 72" diameter pipe.</p>
15	The current bid documents do not include a technical specification for geopolymer line items. Will the Owner incorporate the attached NASSCO specification?	No.